LIBRARY SEP. UNIVERSITY

THE BOSTON
Medical and Surgical
JOURNAL

Published by the MASSACHUSETTS MEDICAL SOCIETY — Official Organ of the NEW ENGLAND SURGICAL SOCIETY

per Annum. 25c per copy
ol. CLXXXIV, No. 23

THURSDAY, JUNE 9, 1921

Published weekly in Boston,
at 126 Massachusetts Avenue

R
11
N57
V.184
no.23
cop.2

CONTENTS

THE MASSACHUSETTS MEDICAL SOCIETY

Shattuck Lecture.

The Prevention of Heart Disease—A New Practical Problem.
By Haven Emerson, A.M., M.D., New York.

ORIGINAL ARTICLE

The Essential Factors of Cancer Causation.
By James W. Shannon, M.B., San Diego, Calif.

EDITORIALS

Mutual Insurance for Physicians.

Narcotic Registrants Must Register this Month.

For complete table of contents, see first text page.

PUBLISHED IN DECEMBER
REPRINTED IN FEBRUARY
AGAIN REPRINTED IN MARCH

Bandler's The Endocrines

To those who have read Dr. Bandler's "The Endocrines," its striking success does not seem remarkable, because the work is one of real merit and practical value. Dr. Bandler's book emphasizes the clinical side of endocrinology—the therapeutic application of our knowledge in the treatment of disease.

Dr. Bandler's book covers the subject completely. It appeals to the practitioner because it gives him the modern conception of endocrinology. It appeals to the diagnostician because it stresses the diagnosis of many conditions that are frequently wrongly attributed to some secondary cause. It appeals to the neurologist, the alienist, and the criminologist because it shows conclusively that the endocrines are directly responsible for many nervous conditions, for abnormalities of mind, and for criminal minds. It appeals to the gynecologist, because it is here the greatest advances have been made. Dr. Bandler used glandular extracts with success before others would credit the value of such therapy.

In the "Cases and Clinics," you get the actual diagnosis—the exact treatment. The dangers of half knowledge are here made clear. There are many conditions in which several glandular extracts are necessary to effect the relief sought. Where one might harm, a number together form an harmonious whole. You are told, in these cases, just what treatment to use and how to apply it.

Octavo of 486 pages. By S. Wyllis Bandler, M.D., Professor of Gynecology, New York Post-Graduate Medical School and Hospital. Cloth, $7.00 net.

W. B. SAUNDERS COMPANY — Philadelphia and London

Entered at the Post-office at Boston as second-class matter.

Has finally demonstrated the fallacy of the so-called uric acid solvent therapy (lithia, etc.) and made unnecessary the employment of Colchicum with its always to be feared deleterious effects on heart and intestines.

Accomplishes a definite scientifically and clinically established physiologic stimulation of the uric acid excretion. Performed innocuously and controllable to a nicety by dosage and by urine and blood tests.

Information, Literature and Ample Trial Quantity from

SCHERING & GLATZ, INC.
150 Maiden Lane, New York

GOUT

HAY FEVER MEMORANDA

(SERIES II.)

Late Spring Type. Patients whose hay fever develops in the latter part of May, or during June, should be tested with the pollens of the chief grasses, such as orchard grass, timothy, red-top—and certain flowering weeds.

Late Summer Type. Patients whose hay fever develops in mid-August and continues until frost, should be tested with the pollens of such weeds as ragweed and goldenrod, the related sunflower, also with the pollens of the one important late flowering grass, viz. corn, if exposed to same.

ARLCO-POLLEN EXTRACTS

For Cutaneous Tests and Treatment cover early and late spring, also summer and autumn.

Literature and List of Pollens on Request.

THE ARLINGTON CHEMICAL CO.
Yonkers, New York

Digitan (Digipuratum)

Physiologically Standardized Digitannoids

This product, first introduced as Digipuratum, is manufactured under license from the Federal Trade Commission and carefully standardized according to the original tests.

RAPID AND RELIABLE IN ACTION

UNIFORM IN STRENGTH

Supplied in Powder and 1½ Grain Tablets

1 tablet Digitan or 1½ grains powder equal to 1½ grains strongly active digitalis leaves (=8 frog units).

MERCK & CO.,

New York and St. Louis, Mo.

In summer diarrhea, intestinal catarrhs, etc.

Tannalbin

DOSE: Infants: 2 to 6 grains several times a day in gruel. Children: 7½ to 15 grains. Adults: Half a teaspoonful (15 to 30 grains in powder or 5-grain tablets) three to five times a day at hourly intervals.

Supplied by the Drug Trade in 5-grain Tablets and Powder

For Literature and Samples apply to E. BILHUBER, Inc., 45 John Street, New York

Organotherapeutic Suggestions

HYPERTENSION

Functional high blood pressure has been reduced repeatedly by **No. 30—Caps. Thyro-Pancreas Co. with Ovary** (for women especially at the menopause, or **No. 29—ditto with Spermin** (for men). The essential principles involve the antagonism between the pancreas and the adrenal pressor function, the cell-stimulating effect of thyroid and the tonic value of the sex-gland principles. Provided the tension is not organic, it may be reduced from 20 to 100 mm. by this method. Dose: 1, q.i.d., or, occasionally, 2, t.i.d.

Results from Adrenal Support

"For years I have fallen down on many cases of neurasthenia and those tired-out 'no-goods' that so often bother us. Your ideas about hypoadrenia and your Caps. Adreno-Spermin Co. have been a surprise. The results are nothing short of wonderful. . . ."

THE REASON

Adreno-Spermin Co. (Harrower) contains suitable doses of thyroid (to increase cellular oxidization), adrenal (to support the depleted adrenals), and spermin (to serve as a muscular and cellular stimulant). The excipient is calcium glycerophosphate. Try one q.i.d. in a few cases and see how it raises low blood pressure, increases 24-hour urea and generally antagonizes "peplessness."

The booklet "*Adrenal Support*" will be sent to interested physicians on request.

THE HARROWER LABORATORY

New York, 31 Park Place — Chicago, 180 N. La Salle St.
Baltimore, 4 E. Redwood St. — Portland, Ore., 610 Pittock Block
Denver, 621 Central Savings Bank Bldg.

Note: There are still several copies of the 272-page, cloth-bound $2.50 book, "Practical Organotherapy," available. Get a copy at once by sending only 25 cents for delivery charges.

Physicians have found that

COMPOUND

Urimene Powder

is valuable as a
"clean-up" treatment,
during or after any infection,
eliminating the toxins
from the system

An excellent antiseptic
and saline eliminant
for use in cases of

Intestinal Fermentation
Auto-Intoxication
Cystitis

Albuminuria of Pregnancy
and
Rheumatic Conditions

COMPOUND URIMENE POWDER
contains
(in each dessertspoonful)

URIMENE (Hexamethylene)	5 grs.
ACID SODIUM PHOSPHATE	30 grs.
LITHIUM CITRATE	5 grs.
SODIUM SULPHATE	8 grs.
SODIUM TARTRATE	q. s.

THREE SIZES
Small, Medium and Large

WOULD YOU LIKE A SAMPLE?

The E. L. PATCH COMPANY

STONEHAM 80, BOSTON, MASS.

INTERNATIONAL POSTGRADUATE COURSE OF THE VIENNA FACULTY OF MEDICINE.

The following lectures will be held from June 6 to 18, 1921, from 8 to 11 A.M. and from 4 to 7 P.M., and will deal with the subject

RECENT ADVANCES IN SURGERY, ORTHOPEDICS, GYNECOLOGY AND PEDIATRICS.

Monday, June 6, from eight to ten-thirty A.M., Prof. Eiselsberg, Surgery of the Thyroid Gland; from ten-thirty to eleven, A.M., Prof. Albrecht, Pathology of the Lymphatic Glands; from four to six-thirty P.M., Prof. Salzer, Infectious Diseases in Surgery; from six-thirty to seven P.M., Prof. Russ, Bacteriology of Infectious Diseases in Surgery.

Tuesday, June 7, from eight to eleven A.M., Prof. Marburg and Prof. Ranzi, Increased intracranial pressure; from four to six-thirty P.M., Prof. Pupowac, Surgical transplantation; from six-thirty to seven P.M., Prof. Haberda, Legal Responsibility of the Surgeon.

Wednesday, June 8, from eight to nine A.M., Doz. Denk, Lung Surgery; from nine to ten A.M., Dr. Sgalitzer, Roentgen Diagnosis in Thoracic Surgery; from ten to eleven A.M., Prof. Wenckebach, Adhesive Pericarditis; from four to six-thirty P.M., Prof. Albrecht, Modern Treatment of Wounds; from six-thirty to seven P.M., Prof. Meyer, Theory of Narcosis.

Thursday, June 9, from eight to ten A.M., Prof. Pal and Prof. Heyrovsky, Cardiospasm; from ten to eleven A.M., Prof. Lotheissen, Strictures of the Esophagus; from four to six P.M., Prof. Schlesinger and Prof. Schnitzler, Intestinal Obstructions; from six to seven P.M., Prof. Kovacs, Subphrenic Abscess.

Friday, June 10, from eight to eleven A.M., Prof. Singer and Prof. Finsterer, Gastro-intestinal Hemorrhage; from four to seven P.M., Prof. Lorenz, Diseases of the Liver and of the Bile Tract; Prof. Eppinger, Diagnostic Value of Jaundice.

Saturday, June 11, from eight to eleven A.M., Prof. Ortner and Prof. Hochenegg, Appendicitis; from four to six-thirty P.M., Prof. Fraenkel, Osteomyelitis; from six-thirty to seven P.M., Prof. Erdheim, Pathological Anatomy of Ricketts, Osteomalacia, and Osteoporosis.

Sunday, June 12, Excursion to the Semmering.

Monday, June 13, from eight to ten-thirty A.M., Prof. Kienböck, Roentgen Diagnosis of Diseases of the Bones and Joints; from ten-thirty to eleven A.M., Prof. Ewald, Modern Treatment of Fractures and Dislocations; from four to five P.M., Prof. Frisch, Treatment of Ununited Fractures; from five to six P.M., Doz. Demmer, Ambulatory Treatment of Fractures; from six to seven P.M., Dr. Lenk, Roentgen Treatment of Surgical Diseases.

Tuesday, June 14, from eight to eleven A.M., (Orthopedic Hospital, V, Gasserg. 44.) Professor Spitzy, Tuberculosis of the Bones and of the Joints; Prof. Spitzy, Operative Treatment of Paresis; from four to six-thirty P.M., Prof. Falta, Chronic Arthritis; from six-thirty to seven P.M., Doz. J. Bauer, Relations of Internal Secretion to the Metabolism of Calcium Salts.

Wednesday, June 15, from eight to nine A.M., Doz. Hass, Causes, Origin and Prophylaxis of Deformities; from nine to eleven A.M., Prof. Lorenz, Diseases of the Hip Joint; from four to six-thirty A.M., Prof. Thaller, Roentgen Treatment of Benign Gynecological Affections; from six-thirty to seven P.M., Prof. Weibl, Treatment of Uterine Carcinoma.

Thursday, June 16, from eight to nine A.M., Prof. Halban, Relation of Internal Secretion to Gynecology; from nine to ten A.M., Prof. Jagic, Clinical Aspects of the Climacteric; from ten to eleven A.M., Doz. Frankl, Early Diagnosis of Uterine Carcinoma;

(Continued on page vi.)

SACRO-ILIAC

SUPPORTERS

A SPECIALTY

100% Efficient. Make Us Prove This

Elastic Stockings, Anklets, Knee Caps, Abdominal Supporters. Custom and Ready Made.

All kinds and styles of supporters for umbilical hernia, weak back, prolapsed stomach, large abdomen and after all abdominal operations or any weakness requiring support.

These Goods Manufactured by Us on Premises

Buy direct from the maker this time and see the difference in fit, quality and service.

EVERY MAN TO HIS TRADE

W. H. PHELPS & COMPANY

156 Washington St. (Adams Square) BOSTON, MASS.

Established 1832 HALL & CARTER, Props Open Sat 9 P.M.

A FEATURE OF

F. H. Thomas Company's SERVICE

Our Surgical Instrument Repair Shop can save you expense by reclaiming your old instruments,—Sharpening, Plating and Adjusting at Reasonable Charges.

Our Shop also has facilities for turning out special work according to specification.

A Highly Specialized Product of this Shop is the THOMAS HAND-FORGED SCALPEL AT TWO DOLLARS.

F. H. THOMAS COMPANY
689-691 Boylston Street
Boston, Mass.

B. B. CULTURE

A pure culture of Bacillus Bulgaricus, eminently suited for use wherever the lactic treatment is indicated,—internally and externally.

B. B. CULTURE LABORATORY
INCORPORATED
YONKERS, NEW YORK

"E.F.M." Perfect Catgut

The Catgut with a reputation for

Sterility—Suppleness
Strength

The "E. F. M." Catgut is found in the operating rooms of most of the hospitals in New England and is used by many of the most prominent surgeons. They realize that the "E. F. M." is the last word in catgut production.

E. F. Mahady Company

671 Boylston Street BOSTON, MASS

(Continued from page iv.)

from four to six-thirty P.M., Prof. Latzko, Peritonitis; from six-thirty to seven P.M., Prof. Adler, Meno- and Metorrhagia.

Friday, June 17, from eight to ten-thirty A.M., Prof. Peham, The Post partem Period; from ten-thirty to eleven A.M., Prof. Hitschmann, Placneta Previa; from four to five P.M., Prof. Moll, Prematnre Children; from five to six P.M., Prof. Zappert, Nervous Diseases in Infants; from six to seven P.M., Prof. Friedländer, Surgery in Pediatrics.

Saturday, June 18, from eight to ten-thirty A.M., Prof. Knöpfelmacher, Vitamine Deficiency in Children; from ten-thirty to eleven A.M., Prof. Jehle, Albuminuria in Children; from four to six-thirty P.M., Prof. Schick, Infectious Diseases in Children; from six-thirty to seven P.M., Prof. Pirquet, Recent Method of Feeding Children.

Physicians who desire to take advantage of this program are invited to send their names and their addresses as soon as possible to the Editor of the *Wiener Medizinische Wochenschrift*, Wien, IX. Porzellangasse 22, and arrangements will be made for their accommodation.

There is no fee for these official lectures, which are delivered in German, but a nominal charge of 1000 crowns (about £1.50) to cover expenses. The address of the office of the postgraduate organization in Vienna is, Vienna, IX. Frankgasse 8 (Tel. 10009).

Another series of postgraduate lectnres will be delivered in September, 1921, and will be particularly addressed to the general practitioner, a final series in December, 1921, will deal with the recent advances in Dermatology, Ophthalmology, Oto-, Rhino-, and Laryngology and Urology.

THE POSTGRADUATE ORGANIZATION OF THE VIENNA MEDICAL FACULTY.

Professor Haberda, m. p.

Sherman's Polyvalent Vaccines in Respiratory Infections

A more adequate and rapid immunity is established with polyvalent vaccines than from an infection itself. SHERMAN'S POLYVALENT VACCINES WHEN GIVEN EARLY IN RESPIRATORY INFECTIONS, rapidly stimulate the metabolism and defense of the body with a resultant prompt recovery.

Administered in advanced cases of respiratory infections, they usually ameliorate or abbreviate the course of the disease. Even when used as the last desperate expedient, they often reverse unfavorable prognoses. SUCCESSFUL IMMUNOLOGISTS MAKE INOCULATIONS IN RESPIRATORY INFECTIONS AT THEIR FIRST CALL.

Hay fever, colds, laryngitis pharyngitis, adenitis, catarrh, asthma, bronchitis, pneumonia, whooping cough and influenza are diseases amenable to bacterial vaccines.

Sherman's polyvalent vaccines are dependable antigens

LABORATORIES OF

DAILY USERS OF VACCINES USE SHERMAN'S

G. H. SHERMAN, M.D.
Detroit, Mich. U.S.A.

"Largest producer of stock and autogenous vaccines"

"KELENE"

(Pure Chloride of Ethyl)

for Local and General

ANAESTHESIA

Manufacturers:

FRIES BROS.

92 READE STREET NEW YORK

Sole Distributors for the United States and Canada

MERCK & CO.

New York Montreal St. Louis

Oral Prophylaxis

MOUTH CLEANLINESS is no longer merely a matter of personal inclination or desire; medical men now recognize it as an essential detail in the prevention of disease.

THE MOUTH offers an ideal dwelling place for germs; it is of just the right temperature and moisture, and unless regularly cleansed, there are always enough decomposing food particles in the deep tissue folds and around the teeth to attract and favor the retention of all sorts of pathogenic bacteria.

NEGLECT OF THE MOUTH means a constant invitation to many of the acute diseases.

A CLEAN MOUTH is, therefore, the first consideration in the modern scheme of personal hygiene.

DIOXOGEN—the best and purest peroxide of hydrogen—is an invaluable mouth-cleanser. Owing its antiseptic qualities to pure oxygen—the same agent—that makes sunshine and good air the most efficient of germ-destroyers, Dioxogen penetrates to the deepest recesses of the mouth, where it softens and detaches all accumulated material, and cleanses and purifies everything it touches.

DIOXOGEN is not a mixture containing aromatic flavors or other substances to convey the idea of great antiseptic power. It is, instead, colorless, odorless and almost tasteless, with a germicidal efficiency superior to the solutions of carbolic or bichloride ordinarily used, but without the slightest toxic or irritating effect.

DIOXOGEN, in consequence, can be used as freely as necessary or desired, in even the youngest patients, with absolute certainty not only that it will keep the mouth and teeth in a clean and wholesome condition, but that it will always do its work in a pleasant and agreeable manner.

THE OAKLAND CHEMICAL COMPANY

59 Fourth Avenue
New York City

Adhering to the Obligation

NO one can review the development of modern therapeutics without being profoundly impressed with the importance of the discovery and isolation of Adrenalin.

We are proud of the policy and the enterprise which have made this achievement possible. And, as the logical purveyors to the medical profession of the only natural Adrenalin, we have not been unmindful of the responsibility so great a privilege entails.

For a score of years the unvarying quality of the product has given eloquent evidence of our adherence to that obligation.

And this explains why physicians all over the world find in the use of Adrenalin, the original product, such a peculiar sense of satisfaction. They are firm in their conviction, gained by repeated experience, that the medicament they have chosen will act quickly and surely and with unfailing uniformity.

Parke, Davis & Company

NEURITIS

is one of the many painful conditions amenable to benzyl benzoate medication; another fruitful field for "Benzylets"—conceded to be the best form for the tastless, no-gastric-irritation administration of this safe, non-narcotic analgesic-antispasmodic.

When you write to Baltimore for your sample, please mention the Boston Medical and Surgical Journal.

BENZYLETS **SHARP & DOHME**

Putting yeast to good use in overcoming constipation

ONE of the conclusions definitely established by investigations carried on at Jefferson Medical College, Philadelphia General Hospital and the Roosevelt Hospital in New York is the efficacy of yeast in treating constipation.

Ten cases were treated. Some of these were chronic of years duration. Only one case failed to respond—a case complicated by subacute appendicitis.

The final conclusion of those who treated and observed these cases is: "It seems to us that yeast is essentially indicated in chronic non-obstructive bowel conditions and contra-indicated in the acute conditions."

Feeding experiments on normal persons also carried on at Jefferson Medical College bore out the testimony of these earlier tests on invalids. In a paper entitled "Bakers' Yeast as Food for Man" Dr. Hawk and collaborators write of the first experiment in which yeast was added to and substituted in a high protein defective diet: "This experiment . . . furnished a very nice illustration of the laxative action of bakers' yeast, an action which we had previously demonstrated upon invalids in connection with our therapeutic tests."

The general conclusions about these feeding tests say: "The average individual may ingest yeast sufficient to yield from one to two grams of nitrogen per day, without securing any laxative effect. When as high as four grams of yeast nitrogen are eaten a laxative effect is generally observed and in some cases soft diarrhaeal stools result. This laxative action of yeast may be put to good use in overcoming constipation."

Fleischmann's Yeast is to-day known to the medical world as of "good use in overcoming constipation."

Yeast is a food, digested and absorbed from the bowels as are other staple foods.

Fleischmann's Yeast may be secured fresh daily from all grocers. If the physician prefers, he may write to The Fleischmann Company in the nearest large city and a supply will be mailed direct on the days wanted.

Usual dosage, from 1 to 3 cakes daily before or between meals, plain or in a suspension of water, fruit-juices or milk.

THE FLEISCHMANN COMPANY, *701 Washington Street, New York, N. Y.*

Athenia Corsets

for

Spinal and Abdominal Support

Made on natural lines to fit the average normal figure. Designed with the help and advice of eminent physicians to give support to the natural curve of the spine and abdomen without pressure at the waist or diaphragm.

As no corset will fit every figure, adjustments and alterations are often necessary and should be made under our supervision. For cases where this is impossible, we have prepared careful directions to insure proper fitting.

MANUFACTURED AND SOLD AT

Chandler's Corset Store

50 Temple Place Boston

Established 1897 Telephone Beach 5134

If Your Patients Suffer From

VISIT OUR EXHIBITS
Booth 63, A. M. A., Boston, June 6-10
Booth, 202, Brooklyn, May 2-5.

Glandular Insufficiency

and you desire to be assured of high quality, reliable endocrine products

"Specify WILSON'S"

Ovary	Suprarenal	Brain	Placenta
Thyroid	Corpus Luteum	Orchic	Spinal Cord
Pituitary	Thymus	Mammary	Duodenum

Supplied in Powder, Tablets, Capsules, Singly or in Combination.

The quality of the product can be no better than the soundness of the raw material.

You realize the importance of having prescriptions filled with desiccated substance obtained from absolutely fresh, sound glands.

As a subsidiary of Wilson & Co., Packers, we have the *distinct* advantage of a direct supply of fresh glands.

Prepared from Abattoir to finished Package

"This mark THE WILSON LABORATORIES your guarantee"

4227 South Western Boulevard, Chicago, Ill.

Manufacturers of Standardized Animal Derivatives, Ligatures, and Digestive Ferments

May we place you on our mailing list for "The Autacoid and Suture," our house organ devoted to Glandular Therapy?

Write for Catalog

The Boston Medical and Surgical Journal

TABLE OF CONTENTS

June 9, 1921

THE MASSACHUSETTS MEDICAL SOCIETY

SHATTUCK LECTURE.

THE PREVENTION OF HEART DISEASE—A NEW PRACTICAL PROBLEM. *By Haven Emerson, A.M., M.D.*, New York. 587

ORIGINAL ARTICLE

THE ESSENTIAL FACTORS OF CANCER CAUSATION. *By James W. Shannon, M.B.*, San Diego, Calif. *(continued)*. 608

EDITORIALS

MUTUAL INSURANCE FOR PHYSICIANS. 610

NARCOTIC REGISTRANTS MUST REGISTER THIS MONTH. 611

MEDICAL NOTES. 611

MISCELLANY

NOTICES, RECENT DEATH, ETC. 614

The Massachusetts Medical Society

SHATTUCK LECTURE.*

THE PREVENTION OF HEART DISEASE —A NEW PRACTICAL PROBLEM.

BY HAVEN EMERSON, A.M., M.D., NEW YORK.

IT is said, with much truth of us as physicians, that we know more facts than we use, that it is not knowledge but the application of it that is desired of us. Even at the risk of entering the lists of the propagandists and promoters, of abandoning the fruitful and tempting paths of scientific study for the sake of exploiting well known facts, I venture to distract you for the brief period of our meeting, from your devotion to treatment of the individual, and to encourage your ever increasing interest in a phase of preventive medicine which seems to me to offer a new field of triumph to our profession.

Theodore Janeway, in the Shattuck Lecture of 1916, said: "The need of the moment, therefore, is for more knowledge; not more knowledge of the dangers of circulatory diseases for the public, which means propaganda, but more knowledge of their causes for the physician, which means ceaseless investigation." And so the need of the moment was, and still the need exists, and always will, and yet there is so much known of causes of deaths that might have been postponed, of sickness that should have been abbreviated, of resources for salvage of the handicapped, that we can no more await the complete array of facts before mobilizing our resources than we could justify withholding vaccination until the etiology of smallpox is established. So, while the strongest call to the physician will, and always should, be to ferret out the causes of disease and ever extend the realm of preventable disorders, and while the voice of such rare and precious students and teachers as Theodore Janeway still calls clearly and true to the clinician, the physiologist, the pathologist, to combine in their assaults upon our own ignorance and nature's secrets, may there be heard also the plea for those whose lives are jeopardized because of lack of industry in the use of the tools of our trade already sharpened and at hand.

In speaking of cardiac disease, let me, for convenience, include the four titles of the international list of causes of death: angina pectoris, pericarditis, acute endocarditis, and organic heart disease, which, in spite of minor errors, have been used with fair consistency for many

* Presented at the Annual Meeting of the Massachusetts Medical Society, Boston, May 31, 1921.


DEATH RATES FOR ALL AGES
NEW YORK CITY, 1911-1920
NUMBER
ALL CAUSES
FOUR CARDIAC DISEASES
TUBERCULOSIS (ALL FORMS)
CANCER
18
16
14
12
10
8
6
4
2
0
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920

CHART A.

years, and with such uniformity as the shifting fashion of clinical nomenclature permits.

My objective will be to persuade you that it is within the realm of possibility, within the reach of present day medical and social knowledge and resources to make as much reduction in sickness and premature death from heart disease as has been obtained by teaching, by diagnosis, by organized medical services in the control of tuberculosis. We have seen first one and then another of the national volunteer efforts in preventive medicine abandon the exclusive methods and arguments of the fanatic, the dramatic appeals of the hobbyist, and arrive at a stable program of endeavor which accepts and includes the facts that disease control depends on a general elevation of the health of all people, and that no age, sex, occupation or race group can long maintain an advanced position of healthfulness without the interest and assistance of all the rest.

The tuberculosis campaigners first recognized that their own special problem could best be helped by their engaging in attack upon all sickness. The devotees of the unborn babe, of the school child, of the blind, and latterly the banded hosts attacking venereal disease and mental disorders, have all come to see the unity of their interest in, and dependency upon, the general health level of mankind and his environment, whether in home, shop, or field.

The infant, the almost embryonic effort at control of our greatest single group of causes of death, at the very start finds its success or failure inextricably bound up with those various preventable diseases of infection, of occupation, of habit, of inheritance, which play a dominant part in the lives and hazards of each age group. In one sense, then, we cannot escape the conclusion that the chief excuse for singling out heart diseases as worthy of selected attack is that we can, perhaps, in this way obtain attention and consideration for a large group of the unnecessarily handicapped, and rouse a determination to put an end to recruiting among the healthy childhood of the nation for the invalids of middle age.

Following the methods of the epidemiologist, let us outline the bulk and location of our disease group. Without going into ponderous details, one can see at a glance the uniform and practically universal preëminence of the heart diseases as a cause of death.

While, up to ten years ago, tuberculosis kept pace with organic heart disease for first place among the causes of death, recently the steady decrease in deaths from all forms of tuberculosis has left heart disease in a position of single eminence. Deaths from the four heart diseases, in New York City, during the past ten years, have been at no time less than 200 per annum per 100,000 of population, and since 1915, all forms of tuberculosis have caused less than 200 deaths annually per 100,000 population, and in 1920 caused not more than 126 per 100,000.

On Chart "A" are shown the crude death rate per 1,000 of population, the death rates for the four cardiac diseases, for all forms of tuberculosis, and for cancer, in New York City, for the years 1911 to 1920.

The following table gives the figures from which the chart was drawn:

Death Rate Per 1,000 of Population	1911	1912	1913	1914	1915	1916	1917	1918	1919	1920
All Causes	15.30	14.41	14.21	14.03	13.93	13.89	13.70	16.71	13.35	12.93
Four Cardiac Diseases	2.	2.01	2.07	2.11	2.17	2.13	2.17	2.32	2.00	2.13
Tuberculosis, all forms	1.89	1.96	1.99	2.00	1.96	1.82	1.88	1.84	1.52	1.26
Cancer	.79	.82	.83	.87	.88	.88	.90	.89	.92	.93

In the state of Massachusetts, with an estimated population of 3,827,329, as of July 1, 1919, there were 7,596 deaths from the four cardiac diseases during the year, or a rate of 198.4 per 100,000; the rates for these diseases separately being, for pericarditis, .7; acute endocarditis, 7.; angina pectoris, 9.7; and for organic heart disease, 181. per 100,000 of the population.

When we study the distribution of these deaths throughout the year, we find a curve of incidence not very different from that of the respiratory group of diseases. (Chart "B"). The heavy loss of life from cardiac diseases occurs in the months of October to May, and when respiratory disease is prevalent, of whatever nature, the deaths from cardiac diseases rise at once. The uniform distribution of cancer is shown in comparison with the seasonal variations of pulmonary tuberculosis and organic heart disease in the experience of New York City for the years 1914-19.


Z-6
COMPARISON OF MORTALITY
NEW YORK CITY 1914—1919 BY MONTHS
ORGANIC HEART DISEASE
PULMONARY TUBERCULOSIS
CANCER
1914
NUMBER
TOTAL
10,038
8,918
4,467
1915
10,383
8,825
4,607
1916
10,687
8,411
4,701
1917
11,110
8,824
4,968
1918
12,103
8,770
4,924
1919
10,435
7,395
5,147
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec

CHART B.

That this is not merely an urban phenomenon can be seen from Chart "C," which shows the assembled experience of the same six years in the rural population of the registration states of the United States, representing an experience of 261,609 deaths from cardiac disease in a population rising from 30,520,275 in 1914.

The table from which the Chart "C" was drawn follows:

Number of deaths from organic diseases of the heart, by month of death, 1914 to 1919, in the rural part of the registration states as constituted in 1914.

Year	Number of deaths from organic diseases of the heart.												
	Total[1]	January	February	March	April	May	June	July	August	September	October	November	December
Rural part of Registration States as of 1914*													
1914	40,726	3,959	3,537	4,140	3,807	3,586	3,044	2,945	2,860	2,915	3,062	3,228	3,703
1915	42,755	3,964	3,624	4,400	4,152	3,586	3,144	3,175	3,038	3,025	3,264	3,271	4,061
1916	44,645	4,854	4,118	4,301	3,807	3,764	3,422	3,276	3,033	3,098	3,286	3,571	4,120
1917	46,354	4,865	4,375	4,416	4,093	4,066	3,642	3,369	3,094	3,208	3,603	3,550	4,093
1918	48,388	4,329	4,017	4,309	4,258	3,826	3,377	3,291	3,100	3,259	4,539	3,776	4,508
1919	40,741	4,251	3,601	4,059	3,755	3,599	3,010	2,982	2,845	2,874	2,942	3,323	3,705
Totals													

*Exclusive of North Carolina, which included only municipalities having a population of 1,000 or more, but less than 10,000, in 1910.

NOTE: [1]The "rural part of registration states" embraces the area outside of municipalities of 10,000 population or more in 1910. The estimated mid-year population, 1914, of the rural part of registration states as of 1914 is 30,520,275, based on the Federal censuses of 1900 and 1910.

The same regular seasonal variation appears and the similarity of the curve of 1914 to that of the combined six years is striking:

The year 1918 is shown to illustrate the two peaks of high death incidence caused in the rural areas of the United States registration area, as in the urban population of New York City, by the 1918 epidemic of influenza. Chart "D" records the same facts as Chart "C," but by the methods of ratios instead of by the method of differences.

A still further evidence of the similarity of cardiac disease death rates among all groups of population is found in the experience in New York City and State, for example, in 1920. Here the death rate per 1,000 of the population from organic heart disease, acute endocarditis and angina pectoris combined in New York City (population, 5,665,148) was 2.13; in the state, exclusive of New York City, (population, 4,785,586) was 2.40; and in the rural population of New York State (population, 2,258,717) was 2.50, an increase which could only be adequately explained by an analysis of the age groups of these three populations.

Analysis of cardiac deaths by age groups shows their relation to deaths from all causes. (Chart "E.") Here the death rate at the several age groups per 1,000 living in the group, is indicated as rising gently from early infancy until the age group 35-45, when the rate rises rapidly.

While the death rate from cardiac diseases in the age group 25-30 represents 9.1% of all deaths at this age group, the cardiac disease deaths at the age group 35-45 are 13% of all deaths at this age group, and cardiac deaths at the age group 55-65 are 23% of all deaths at this age group.

The figures from which Chart "E" was drawn are given in the following table:

Rates for 1000 population at age groups.

	Under 5	5-10	10-15	15-20	20-25	25-30	30-35	35-45	45-55	55-65	65+
All Causes	31.8	3.5	2.	3.	4.3	5.6	7.7	11.6	22.3	44.8	102.4
Four Cardiac Diseases	.14	.33	.41	.39	.58	.51	.79	1.47	3.91	10.09	29.10

On further splitting up our problem into its smaller elements, it will be seen by a study of Chart "F" that pericarditis, angina pectoris, and acute endocarditis play a relatively insignificant part in the total deaths from cardiac diseases at whatever age group. Distributing the deaths from the four cardiac diseases for the ten years 1911-20 in New York City by 18 age groups, we get a picture from which we can draw valuable lessons for a preventive campaign. Whatever measures we may find suitable to apply will certainly have to bear largely upon the age groups under 15.

This chart shows the actual differences in numbers of deaths at each age group, and in this method of graphic representation much is lost which can be shown best by using the semi-logarithmic method, or the chart of ratios (Chart "G").

Here the same facts are recorded as appear

DEATHS FROM FOUR CARDIAC DISEASES RURAL REGISTRATION AREA — BY MONTHS

(POPULATION FOR 1914 – 30,530,275. TOTAL DEATHS 1914 – 1919 — 261,609.)



CHART C.

on Chart "F," but the per cent. of increase from one death to 10 has the same value in the curves as the per cent. of increase from 10 deaths to 100, or from 1,000 to 10,000. By this method one can exhibit on the same chart the differences of age group distribution of deaths from cardiac disease, such as angina pectoris, with not more than 400 deaths at any one age group, and deaths from organic heart disease with 13,000 at the same age group. If we plot statistical curves of widely different magnitudes on the same drawing, and if our object is to compare not only the amounts of increase or decrease, but the percentage rates of change, there is only one correct method: the semi-logarithmic chart.

The almost uniform number of deaths from acute endocarditis at each age group up to 55, and then the sharp drop, and the quite similar curve of pericarditis deaths contrast sharply with the sky-rocket curve of angina pectoris in the age groups over 15 years, and the more gradually mounting curve of organic heart disease to the age group 60-65.

The significance of the variation in deaths at the several age groups would be largely lost if we relied only upon the chart of differences (Chart "F"), instead of using the method of ratios, as shown in Chart "G."

To quote from a brief statistical survey of the importance of cardiac deaths, by Louis I. Dublin:—

"Under 25 years of age, organic heart disease causes as many deaths as typhoid fever;

"Between 25 and 34 years, organic heart disease causes as many deaths as lobar pneumonia;

"Between 35 and 44 years, organic heart disease causes more deaths than Bright's disease;

"After 45 years, organic heart disease shows a higher death rate than any other cause."

Of the amount disbursed in death claims by the Metropolitan Life Insurance Company in 1920, over $5,000,000 were paid on account of deaths from organic heart diseases. To quote further from the same statistical bulletin of the company (February, 1921), with regard to loss in expectation of life on account of organic heart diseases, we learn that there is a curtailment of two years of life expectation among females, and one and two-thirds years among males, this loss being heavier among white people than among colored. This loss in life expectation is greatest about the age of five and continuous up to and beyond the age of 75, as can be seen from the accompanying table:

	WHITE		COLORED	
Age	Male	Female	Male	Female
0	1.67	1.98	1.57	1.87
1	1.86	2.17	1.87	2.18
2	1.91	2.21	1.97	2.29
3	1.94	2.24	2.01	2.33
4	1.95	2.26	2.03	2.35
5	1.95	2.27	2.03	2.37
15	1.93	2.25	2.08	2.43
25	1.89	2.23	2.15	2.54
35	1.88	2.19	2.23	2.60
45	1.87	2.12	2.17	2.44
55	1.81	1.99	1.95	2.11
65	1.56	1.68	1.62	1.68
75	1.19	1.21	1.27	1.23
85	.96	.82	.99	.85
95	.41	.42	.33	.36

Whether or not cardiac diseases are increasing as causes of death, need not concern us here, and it is, to say the least, doubtful whether any valid thesis to this effect can be maintained in view of the lack of uniform methods of diagnosis and certification of death from generation to generation. It would appear that the last twenty years have developed an increase in death rates from cardiac diseases, especially at the older age groups, but the elements of error are too great for us to accept any such statements as final.

We are in the same dilemma in our study of heart disease as we are in most other matters of disease prevalence, since deaths and death rates bear about as much relation to the problem of the suffering human as the ash dump does to the life of the industrial plant. We have no adequate morbidity data of any disease, and the methods of survey of hospital, dispensary, or private practice experience leave much to be desired. Although we can estimate with considerable accuracy the true incidence of typhoid fever, from deaths occurring from this disease, we have no ratio of percentage based on any recorded experience to indicate how many people in a community are in all probability suffering from heart diseases when we have recorded the deaths. We have certain broad experiences, however, that approximate the truth probably as nearly as we can in tuberculosis.

About 5% of the men called in the drafts were rejected because of disabling heart disease. About 2% of the food handlers in New York City were found to have clinically important heart disease. About 2% of life insurance applicants are rejected because of cardiac disease. About 2% of the children in school populations are found to have some cardiac disorder.

DEATHS FROM FOUR CARDIAC DISEASES RURAL REGISTRATION AREA BY MONTHS

(POPULATION FOR 1914-30,530,275. TOTAL DEATHS 1914-1918-261,609.)



MADE BY GRAPHIC REPRESENTATIONS SECTION — BUREAU OF WAR RISK INSURANCE — C. H. F.

CHART D.

Further study of the latter experience, the only one of the four so far followed through by systematic medical and nursing supervision, shows that probably not more than one-half of those with signs of cardiac abnormality of sound or function are suffering from disorder of such nature as to require medical care and direction. Taking the community as a whole, we may be within the truth if we estimate that not more than 2% and not less than 1% of the total population at any time need care and medical assistance because of heart disease.

The percentage of children in public and parochial schools of New York City found to have cardiac diseases among those examined by medical inspectors of the Department of Health, is shown in the following table:

	1915	1916	1917	1918	1919	1920
Number of Children Examined	278,174	276,611	328,190	247,735	248,978	243,418
Number with Cardiac Diseases	1.5	1.9	1.8	1.6	1.5	1.3

In sickness surveys made by the Metropolitan Life Insurance Company, which included the experience among 571,757 persons, organic diseases of the heart were exceeded only by external violence, rheumatism, influenza, pneumonia, tuberculosis, diseases of the stomach, and apoplexy as disabling sicknesses.

A gradual increase in the incidence of cardiac diseases and chorea among 356,292 school children during their school years, as found by examinations by the medical inspectors of the New York City Department of Health, has been reported by Dr. S. Josephine Baker, both boys and girls showing about twice as high an incidence of both these groups of disorders at ages 14 and over, as they are found to have at the age of eight.

To follow the method of presentation so effective in attracting the attention of laymen to the seriousness of the tuberculosis problem, we may say with reasonable accuracy that cardiac diseases are responsible for one in every six or seven deaths (tuberculosis is responsible for one in every ten deaths). More than one per cent. of the entire population is suffering from some form of organic heart disease (one per cent. has active pulmonary tuberculosis).

There are from five to nine cases of heart disease for every cardiac death per annum (there are probably nine to ten known active cases of pulmonary tuberculosis for every death from this disease per annum).

It will be accepted, therefore, that the detection of cases of cardiac diseases in their incipiency is important to the community for the prevention and postponement of disability and death. As in the wise plan for the control of tuberculosis, periodic medical examinations, especially trained consultants to counsel with the general practitioner, and medical supervision of school children and industrial workers have been found effective, so we may expect similar benefit by the same methods in an attack upon heart disease.

There is lacking any clinical or pathological information upon which could be based even a presumptive curve of the incidence of cardiac diseases by age groups.

The ages at which the communicable diseases chiefly occur, which we believe are responsible for the majority of cases of valvular and muscular diseases of the heart, certainly fall in the age groups under 35, and a majority before the age of 10, and perhaps, the largest number for any one age group before the age of 5.

In support of this very general statement, permit me to report upon the experience of some of the special cardiac clinics of the Associated Cardiac Clinics in New York City. A total of 6808 patients are reported upon, of whom 4392 were active cases on May 1, 1921; that is, were in regular attendance or under supervision of the visiting nurse of the clinic.

Among the adults of this group, the histories of 927 appear to have been so carefully analyzed as to permit of a sound opinion as to the probable causative infection, as follows:

In 331 cases,	acute rheumatic fever
207	acute tonsillitis
122	syphilis
78	scarlet fever
47	diphtheria
14	pertussis
54	measles
163	carious teeth
7	chorea
927	

Of these patients, 614 were active cases in regular contact with the clinics on May first.

In attempting to obtain similar facts from the histories of the children attending special cardiac clinics, the problem is more difficult, be-


DEATH RATE PER THOUSAND BY AGE GROUPS
NEW YORK CITY; 1917.
·····CARDIAC DISEASES (Organic Heart Disease, Acute Endocarditis, Angina Pectoris and Pericarditis.)
——ALL CAUSES
NUMBER
140
120
100
80
60
40
20
0
13.70
CRUDE DEATH RATE, ALL CAUSES, ALL AGES
13.70
Under 5
5 to 10
10 to 15
15 to 20
20 to 25
25 to 30
30 to 35
35 to 45
45 to 55
55 to 65
65 & Over
MADE BY GRAPHIC REPRESENTATIONS SECTION BUREAU OF WAR RISK INSURANCE C.B.W.

CHART E.

cause the records show all the infections, and in many instances several prior to the onset of reported symptoms of heart disease. In most instances the clinic physicians have quite properly refrained from committing themselves to the particular one of several infections which was thought to be the actual exciting cause of the cardiac involvement.

Among 720 children patients at these cardiac clinics where case histories were particularly well reported and studied, infections as possible or probable chief etiological factors were given as follows:

(Two or more of the following infectious conditions were reported in many cases.)

In 279 cases,	acute rheumatic fever (growing pains, etc.)
282	acute tonsillitis or sore throat
——	syphilis
53	scarlet fever
63	diphtheria
130	pertussis (at one clinic only)
232	measles
207	carious teeth (none at one clinic)
49	chorea (none at two clinics)

Ledford[1] has recently reported that in 86.8% of a group of 250 cases of acute endocarditis in a children's hospital ward, the cardiac infection followed directly acute rheumatic fever, chorea, or tonsillitis. So sharp-cut a statement can rarely be made for the patients who come with an established valvular heart lesion and a history of a multitude of infections. While the ultimate classification of all or even the most important direct etiological factors in causing organic heart disease must await more precise knowledge we can, for convenience in guiding the always elusive public health educator and propagandist, with safety state that of the infections, syphilis and rheumatism are positive causes, that diphtheria, typhoid fever and scarlet fever are presumptive causes, that measles and whooping cough are under serious suspicion, that infected tonsils and diseased teeth and cryptic foci of various kinds may, in many cases, prove to be the true cause of what is called rheumatic or cardiac infection, that senescence, arterial hypertension with or without renal disease, and the insidious diseases of occupation which are often mistakenly reported as arteriosclerosis, play a large but wholly undetermined rôle. The elements leading to extension of existing lesions, to the disturbance of mechanical equilibrium of a heart developed to compensate for an orderly and well adjusted activity, are so multifarious and fall so clearly within the clinical field that I shall make no attempt to comment upon them, except to say that from the assembled reports of many patients under specialist clinic control in New York City, the impression grows constantly stronger that re-infection and a state of poor nutrition and inadequate sleep and rest are more common, potent and serious causes of renewed or original decompensation than are sudden overexertion of physical strain in play and work. It becomes more apparent that the immediate needs of the clinician and the remoter but none the less vital needs of the community can be met best by a central office or library of clinical records assembled on sound statistical lines.

What is important to obtain but not yet available, is a careful clinical and pathological study of the age at infection or onset of valvular or other organic heart disease. The material is now at hand and developing day by day in the practice of a multitude of physicians throughout the country, but is nowhere assembled, and, as a rule, the fact of cardiac involvement after any infection is not recorded or remembered, and the date of onset or invasion is a matter of mere guess work when the mechanical end results of the disease have brought the patient under medical care.

Among dispensary patients, most of the children have had the usual communicable diseases and frequently, also, have passed through attacks of the respiratory diseases, such as pneumonia and influenza. Reliable history by parent or child as to the prior importance or even occurrence of rheumatic or tonsillar infection is rare.

While referring to the clinical material under observation at 29 or the 31 cardiac clinic classes in New York City, for which reports have been available, it is worth while to consider the relative adequacy for the estimated need of a community for the services now provided in New York City in this field. Here again, we can with benefit use as a basis for comparison the well established services of the tuberculosis dispensaries. There are, and have been for a

[1] Ledford, H. P.: American Journal of Diseases of Children, February, 1921, 21, No. 2.


DEATHS FROM FOUR CARDIAC DISEASES
NEW YORK CITY 1911-1920 BY AGE GROUPS
ORGANIC HEART DISEASE
ACUTE ENDOCARDITIS
ANGINA PECTORIS
PERICARDITIS
TOTAL DEATHS (Four Cardiac Diseases)
NUMBER
13,000
12,000
11,000
10,000
9,000
8,000
7,000
6,000
5,000
4,000
3,000
2,000
1,000
0
Under 5
5 to 10
10 to 15
15 to 20
20 to 25
25 to 30
30 to 35
35 to 40
40 to 45
45 to 50
50 to 55
55 to 60
60 to 65
65 to 70
70 to 75
75 to 80
80 to 85
85 and over
AGE

CHART F.

number of years, in operation in the five boroughs of New York City, 29 tuberculosis dispensaries, and their number and distribution have been found reasonably adequate for the needs of the community, this provision amounting to 10 clinic hours of medical services per week for each 100,000 of population, as compared with 20 in Boston, 13 in Philadelphia, and 10 in Cincinnati, cities in which the field is considered to be well covered. (There are reported to be 550 tuberculosis dispensaries in operation in the United States).

On the basis of the death rate from tuberculosis in New York City, 1920, we can estimate that there are 35,660 active pulmonary cases of the disease, of whom about 27,000 are registered with the Dept. of Health. Of the registered cases, 11% are in attendance at or in contact with the tuberculosis dispensaries, or approximately 3,000. Although we may consider that 2% of the population have cardiac diseases, probably not more than 1% of the population at any one time needs medical supervision for this reason, or 56,651 in 1920. On the basis of the experience with tuberculosis, we may expect about 8.5% of estimated active cases to accept dispensary care, or 4,815. However, since the period of years in cardiac diseases for which medical supervision is desirable is, in the main, much greater than is the case in pulmonary tuberculosis, we may expect a larger attendance year in and year out, from the same unit of population, at cardiac clinics than at tuberculosis clinics.

It is of considerable interest to note that the estimate of expected attendance and needs for dispensary care of cardiac diseases closely approximates the current facts, since there are upward of 4500 active cases in attendance at the 31 special cardiac classes in dispensaries now in operation throughout New York City. The attendance is given accurately for 29 of the 31 classes (4342 on May 1st), the last two having been put in operation too recently to have developed an accurately recorded clientele.

Without going further into the subject of the extent and distribution of cardiac diseases and accepting as proved the major importance of the deaths, the sickness at all ages, the urban and rural incidence, the seasonal distribution of deaths, the effect on life expectation in both black and white races, of the cardiac diseases, and admitting that we are yet without the important facts as to the exact etiologic factor in all cases, or the ages at which the various determining infections occur, let us turn to the problem of providing for such relief from this incubus upon our fellow citizens as we are capable of.

If we look the country over and search for an effective demonstration of an effort to bring to the aid of those already afflicted the best that the medical sciences and social organizations are capable of, I think you will agree with me that the Association for the Prevention and Relief of Heart Disease in New York City must be recognized as having most nearly approached the goal. If we may, as we love to do, think back to the time when what we see now in operation was a vision in the mind of one practical idealist, it seems to me we must give Dr. John Huddleston, the friend and adviser of a multitude of the handicapped and the suffering, full credit for the conception of much of our present program. He had grown up with, and played a leading part in, the development of tuberculosis control and service, of care and prevention, over a period of twenty years before his death, in 1915. He was convinced of the need and the opportunity to organize the always willing but individualistic services of physicians, and the generous but sentimental public for the early detection of heart diseases in children, the provision of such hospital and convalescent beds for those with acute infections as will permit of rest and recovery, instead of permanent mechanical damage of muscle and valves, the orderly and controlled supervision by doctors and nurses devoted to this highly technical specialty, of all those whose usefulness and safety depends upon their learning, as in a post-graduate university of applied hygiene, their limitations and their possibilities the provision of such guidance in school, shop and employment agency for child and man as will set at naught the handicap of the heart by intelligent selection of occupation. The proof that this vision was that of a prophet as well as of a scientist, is the astonishing rapidity with which the ideas took root, the eager workers fell to at the task and the realization of the project has approached a very considerable refinement and success.

It is a matter of especial satisfaction to the associates of this good physician that a fund collected by his devoted patients was turned over to a group of physicians to administer and use in defraying the expense of studies in the


DEATHS FROM FOUR CARDIAC DISEASES
NEW YORK CITY 1911 - 1920 BY AGE GROUPS
ORGANIC HEART DISEASE
ACUTE ENDOCARDITIS
ANGINA PECTORIS
PERICARDITIS
TOTAL DEATHS (Four Cardiac Diseases)
NUMBER
10,000
1,000
100
10
1
Under 5
5 to 10
10 to 15
15 to 20
20 to 25
25 to 30
30 to 35
35 to 40
40 to 45
45 to 50
50 to 55
55 to 60
60 to 65
65 to 70
70 to 75
75 to 80
80 to 85
AGE

CHART G.

problem of home and dispensary direction of children with cardiac diseases. Another fund, for special research work in cardiac disease, has recently been created by Mr. Frank G. Sturgis. The facts as to organization, costs, plans and results of this distinctly medical undertaking can all be more appropriately read from the reports and publications of the Association than in this lecture.

A program for control of heart disease for a city so nearly the population of the Boston metropolitan area, namely, Cleveland, Ohio, as to be entirely applicable to Boston, was prepared a year ago in collaboration with the officers of this Association, and is published as part of the Cleveland Hospital and Health Survey (1920, Part ii, pp. 213-220).

The more important professional results of this movement in New York City have been, first, the assembling for a common purpose of a particularly keen group of students of clinical cardiac disease and their organization into a professional association ready to undertake such mutual studies and to establish such common standards of reports, methods, terminology, etc., as are prerequisites for study of the small army of patients already reporting daily for orders at the dispensaries. Already a terminology is in effect which permits of a common language in discussing patients in bulk, and plans are well advanced for such use of clinic records and their central tabulation and collating that the separate physicians will each be making his important contribution without bearing the, to him, distasteful burden of clerical and statistical analysis. The following terminology is in general use in the dispensary care of cardiac patients in New York City:

FUNCTIONAL CLASSIFICATION OF CARDIACS.

ORGANIC HEART DISEASE.

Class I. Patients who are able to carry on their *full habitual activity.*

Class II. Patients able to carry on *diminished physical activity.*

A. Slightly decreased.

B. Greatly decreased.

Class III. Patients who are able to carry on *no physical activity.*

POSSIBLE HEART DISEASE.

Class IV. Patients who have abnormal physical signs in the heart, but in whom the general picture, or the character of the physical signs leads us to believe that they do not originate from cardiac disease.

POTENTIAL HEART DISEASE.

Class V. Patients who do not have any suggestion of cardiac disease, but are suffering from an infectious condition which may be accompanied by such disease: *e.g.*, rheumatic fever, tonsillitis, chorea, syphilis, etc.

This organization has served to remind us of the unlimited fields of clinical research that can and must be cultivated apart from laboratories, or even hospitals, and carry us into countless homes, the final answer to our questions depending upon the record of a life time. Can we, perhaps, tell our children what is the true cost of a life time of heart disease to the community and to the individual? With 6,000 patients to study, some of the still disputed questions of the etiology also will soon be answered.

For those who wish to undertake the operation of a special class for either children or adults, a warning must be given as to the danger of overloading with patients who cannot be continuously followed up. It is no less dishonest in a dispensary than for a private practitioner to accept responsibility for more patients than he can thoroughly well care for. It is found that not more than 150 active cases can be adequately examined and followed up by one special class. What is considered adequate personnel for one class holding one session a week is:

One physician @ $3.00 an hour	$450 a year
One full time registered nurse	$1800 a year
Clerical help @ $.50 an hour	$100

Space, and suitable office equipment and supplies, light, heat and telephone service, can usually be provided in an existing dispensary plant. A transportation fund will be needed to permit the nurse to visit patients for follow-up, unless the population served is in a small area adjacent to the dispensary. The exact information is not yet available, and yet a sufficient number of cases have so far been studied to make it quite clear that by an expenditure of not to exceed $15.00 a year, not only can the great majority of active cardiac pa-

tients be so guided and supervised as ambulatory patients, from the dispensary or at their homes, that periods of hospital care ($3-$5 per day) are less frequent and of shorter necessary duration, but that the earning capacity of the adults, and the school attendance of children, is increased far beyond the money cost of the dispensary care. As it costs less to save an infant life than to provide its burial expenses, so investment in medical supervision of cardiac patients pays truly astonishing dividends in services to the community and in happiness of life for these handicapped people.

In addition to the 31 special classes for cardiac disease in New York City (14 for children and 17 for adults, several of the latter in the evening), there are known to be in operation 28 more in other of the larger cities in the country.

Albany	1
Boston	8
Chicago	4
Cleveland	1
Des Moines	1
Detroit	1
Iowa City	1
Long Branch	1
Milwaukee	1
Minneapolis	2
Philadelphia	4
Rochester	1
St. Louis	2

The most effective and constructive service for prevention and relief of heart diseases is that close coördination of school and clinic found where the examination of the children picked out by the school medical inspector is taken up by a clinic class operated in the school district, the chief of the cardiac class becoming the specialist adviser for the school and home career of the cardiac school child, just as the tuberculosis specialist has guided the anemic and pre-tuberculous child in the open air classes of the public schools.

There are now 12 special cardiac classes in the public schools of New York City (about 550 open air classes for the pre-tuberculous) each class of about 25 children.

The most ambitious program and the most nearly perfect facilities for school and clinic care of cardiac school children is to be found in the three special classes at 8th Street and Avenue B, where they occupy a building apart from the regular school buildings, provided with certain conveniences, elevators, rest rooms and exercise space, etc., asd their entire régime and individual prescription for physical training, rest, etc., is under the direction of the special clinic at the New York Post Graduate Hospital (Dr. Robert H. Halsey and associates). Details of results of the work in this special group of patients, showing the progress in school attendance, development of cardiac balance, increase in physical fitness, etc., will be presented at the meeting of the American Medical Association next week. It may be stated that one-third of the children picked out as having some cardiac defect of sound or function are found to be in need of medical direction for definite organic cardiac disease. There is great benefit to children in relieving them from the fear of the term, "heart disease," and teaching them how normal and natural their lives may be within wide limits. Supervision produced a gain of 13.5% in school attendance. Expressed in school days, each child gained three weeks of school attendance under special clinic and class care.

The clinicians of these special cardiac classes have before them the questions put to you by Theodore Janeway in 1916: "Whence came these diseases and why? What are their primary, and what their accessory causes? How do they reach their baneful development? On finding the right answer to these questions, depends the final attainment of the goal of our profession, the prevention of disease. By as much as the proverbial value of prevention exceeds that of cure, does the importance of study of the causes of disease surpass that of the manifestations, its results, or its treatment."[2]

We see heart diseases as we have found tuberculosis, venereal diseases, cancer, infant mortality, and blindness, preventable by a multitude of means, each aimed against a specific fact or a direct or immediate effect. Such standards have been put into effect in clinics successfully operated for a number of years, that detailed consideration of their functions, objectives and accomplishments need not be repeated. What is, I believe, the best description of the most complete and efficient medical organization for cardiac children during the non-hospital periods of their lives, has been given in the *Hospital Social Service Quarterly* by Dr. Wm.

[2] Janeway, T. C.: "Etiology of the Diseases of the Circulatory System," Shattuck Lecture, BOSTON MEDICAL AND SURGICAL JOURNAL, June 29, 1916.

P. St. Lawrence and Miss E. Louise Adams, the nurse in charge.

This class for cardiac children at St. Luke's Hospital has been operating for five years and has made important additions to our knowledge of methods and results. While we see the correction of many evils in progress under guidance of such clinics as this, it is well to review the situation of the cardiac child where it lacks special provision. St. Lawrence and Adams have well described it in the introduction of their paper. "In our general Pediatric Clinic, few cases have presented a more pathetic and discouraging outlook than the cardiacs. Their care has been haphazard and, undoubtedly, in many instances, improper. As their lives have been restricted almost to the point of uselessness, they have been a burden to their families and to themselves. Their education and development have been sadly neglected and, in many cases, it has seemed questionable whether life for them was worth while. They have repeatedly sought help which we have not known how to give. In the cases with milder lesions, we have unnecessarily made life a burden. The severer cases have been too forcibly impressed with the certainty of the coming outbreak. Our management has been without plan and has consisted largely of meeting the individual symptoms. In many instances, this has only meant waiting for the eventual failure, with the hospital ward as the ultimate refuge. Discharge and return home has been but the first phase of another cycle, and not infrequently the final cycle was early brought to a close."

The studies upon cardiac tolerance in children, by Dr. May Wilson, at the Nursery and Childs Hospital, the studies under the Huddleston Memorial Fund, by Dr. Charles Hendee Smith and his associates, both already reported upon, and the studies of Dr. John Wyckoff at the University and Bellevue Hospital Medical College Cardiac Class, in etiology and duration of the disease in adults, are a few of the important contributions to medicine of these new clinical services.

Through the courtesy of Dr. Wyckoff, I am permitted to give you the preliminary results of a study of 200 cardiac patients reported from his clinic, as follows:

Of the 100 patients in whom rheumatism, tonsillitis and chorea, together or separately, played probably the exciting etiological rôle (65 males and 35 females), they were distributed as follows, by decades: 10 to 19 years, 24; 20 to 29 years, 39; 30 to 39 years, 16; 40 to 49 years, 15; 50 to 59 years, 5; 60 to 69 years, 1; total, 100.

Of those giving a history of syphilis as the probable primary cause, the distribution was: 30 to 39 years, 3; 40 to 49 years, 8; 50 to 59 years, 10; 60 to 69 years, 2; total, 23.

Of those evidently secondary to some particular septic process, the distribution was: 10 to 19 years, 1; 20 to 29 years, 1; 30 to 39 years, 4; 40 to 49 years, 1; 50 to 59 years, 1; total, 8.

Of the remaining 69, there were secondary to nephritis, 1 at 40 to 49, 2 at 50 to 59, and one unknown; total, 4.

Of the other 65, which include senile and, probably, those of arterial and renal origin, the distribution was: 10 to 19 years, 6; 20 to 29 years 12; 30 to 39 years, 12; 40 to 49 years, 11; 50 to 59 years, 19; 60 to 69 years, 3; 70 to 79 years, 2; total, 65.

Grand total, 200.

The distribution to early decades of those of so-called infectious rheumatic origin was to be expected, and the location of syphilitic hearts in the decades after 30 is also in agreement with the usual incidence of syphilis in the population as a whole, or at least the occurrence of the structural sequellae.

A further analysis of the 100 cases with a probable rheumatic tonsillar or chorea origin, according to the period which elapsed between the date of probable infection and the date when the patient knew he had a cardiac disease, either from appreciation of the importance of the subjective symptoms or by direct statement from a doctor, shows that, on the average, these patients did not know that they had cardiac disease until 5.36 years after infection. The periods, of course varied widely from cases where knowledge was immediate at the time of the acute sickness of origin, to those who had evidently had their disease 30 years before they knew what was the matter with them, a measure of the failure of the patient and the physician to meet, and the latter to meet the full need in each case.

Of the twenty-three syphilities, the average time before knowledge of their cardiac involvement was 17.65 years after infection (the range being from one to 34 years after).

A further interesting point is the length of time after knowledge of infection before pa-

tients first attended a clinic. Of the 100 of the rheumatic group, the average delay was for 8.5 years after knowledge of infection before the patient appealed for relief at the clinic, and with the syphilitic group of twenty-three, the period was 21.4 years.

These are practically all patients of the dispensary class, in whom economic limitations have probably prevented their using medical advice as early as they would have been tempted to if the necessity for continued work had not been so pressing, but the figures are sufficiently impressive to guide us in much of our preventive program.

The cardiac is entitled to education as to the merits of early diagnosis and the difficulties of cure or relief in advanced stages of these diseases, as the tuberculous are, and there can be no doubt that the educational campaign to reach the incipient tuberculous has born fruit, for the percentage of negative cases on first examination and the percentage of incipient cases in the clinic attendance have increased with great rapidity in recent years.

As it was with the tuberculosis movement, so in the present effort to bring service to the cardiac, we find the pressure and initiative strong from the ranks of the social workers' profession. One of the first problems considered by the Hospital Social Conference in New York some ten years ago was the provision of convalescent care and suitable vocational direction, training and employment for handicapped cardiac dependents. No adequate or consistent professional service for cardiac patients can omit the two elements which chiefly contribute to a shortening of periods of total disability, namely, the adjustment of the patient to a substantially gainful occupation suitable to his mental and physical capacities and the completion of the hospital treatment by a convalescent training which will lead directly and, under medical supervision and encouragement, into work instead of dependency. The chronic cardiac, no less than the chronic tuberculous, is always in danger of losing his moral fibre, the essentials of character upon which self-support and self-respect depend, because of the failure of even our best technical medical services to inject into their therapy the element of moral stamina and an outlook of hope and determination instead of permitting a subsidence into the easy indolence of those who enjoy their invalidism.

For information and helpful suggestions as to the problem of employment for cardiacs, and the way it may be met, clinicians, as well as relief agencies and hospital administrators, should study the reports of Mrs. I. M. Duggan, Director of the Employment Bureau for the Handicapped of the Hospital Social Service Association of New York City. The conception of this problem from the hospital point of view, has been nowhere better expressed than in the following paragraphs from Mrs. Duggan's second paper in the *Hospital Social Service Quarterly,* 1920, 11,227:

"As Emerson[3] has well expressed the situation, the hospital enters into a tacit contract with each patient it accepts, that it will try to reach the cause of his disease. But is the hospital, in reality, living up to the spirit of its contract if it does not help a cardiac find a lighter job after his first admission? Is the hospital not squandering trust funds to spend money to treat a patient if they know that the good work done will be quickly lost if he returns to his old occupation? If the proper treatment of a cardiac is not drugs, but a change of occupation, should this not be supplied, just as an operation would be given free to a hernia patient, or quinine to a case of malaria? But objection is made to the cost of supplying the machinery necessary for this placement work. The cost of finding a cardiac lighter work is far less than the cost to the same hospital of this cardiac, who will return repeatedly for longer and longer periods if he is allowed to undertake his former occupation.

If the hospital superintendents would only realize how many days of hospital care could be saved their institutions by the proper employment of cardiacs upon their discharge from the hospitals, we would see an employment bureau for cardiacs, supported by the hospitals themselves, established in every community."

In the field of convalescent care, there have been no more valuable contributions to our knowledge of the technic of institutional care, occupational and recreational training and resources for the immediate post-hospital period for the cardiac patient than have appeared from the experience of the Burke Foundation Convalescent Home at White Plains. The reports and recommendations for this particular type of medical service presented in the last few

[3] Emerson, C. P.: Hospital Social Service Quarterly, 1919, 1, 263.

years by Dr. Frederic Brush, show an increasing accuracy in determining the kinds of patients for whom a wide range of activities are not only permissible but necessary, and a courage in breaking paths into fields of work and play heretofore forbidden to the cardiac.

As a mark to set for future accomplishment by the hospital services of a community, we may use estimates for the need of convalescent beds. If, as seems probable, on the basis of experience in our large cities, we need about five general hospital beds for every 1000 of the population and for every 100 of the hospital patients discharged from care, 12 will need institutional convalescent care (this number to include provision for those needing convalescence, and coming from dispensary and private care), we find that one out of every five convalescent beds will be required for cardiac patients (2/3 of the beds for children under 14). The cost of such care, even including transportation and admission office expenses, is about half the daily cost of hospital care in general hospitals. In New York City, of the 500-600 beds considered necessary for cardiac convalescents for its population, 300 are already available, and others are in preparation. Tentative conclusions have been arrived at for the guidance of those wishing to obtain convalescent care for cardiacs after hospital and dispensary treatment and are here quoted from proposals considered by the Associated Cardiac Clinics of New York City:

"I. Convalescent homes should accept patients with heart disease only after they have been examined at a cardiac clinic.

II. Patients proposed should be held to the following types:

1. Those needing convalescence for other conditions than heart failure, but who may incidentally have heart defects (under Class I of the classification of cardiac patients, as adopted by the Association).
2. Convalescents from acute heart failure, who have been out of bed for some time, in the hospitals or at home, and who show no dyspnea after moderate exercise. (Classes II and III of the classification of cardiac patients, as adopted by the Association.)
3. Patients who are not convalescent from acute heart failure, but who show signs of heart and general fatigue while under observation at the clinic, and who need shorter preventive stay. (Class III of the classification of cardiac patients as adopted by the Association.)
4. Younger persons yield best results and are given preference. [*Note.*—Too few persons are sent of the types indicated under 1 and 3, above.]

III. The following types of patients are not considered suitable for convalescent treatment:

1. Convalescent from acute rheumatic fever, not to be sent until joint symptoms have been absent for three weeks.
2. Cases that show lung congestion, or a tendency to bronchitis or asthma.
3. Persons with marked renal complications.
4. Those mentally, nervously or otherwise unpromising for the essential active cooperation and long stay. This would include patients who are likely to develop homesickness, or who might be unable to adapt themselves to a régime.

IV. The following coöperation shall be given by the submitting agencies:

1. Help to lessen the strain and fatigue of the admission day (transportation to admission office, etc.).
2. Hospitals should take back patients at the beginning of a relapse that may develop while at the home.
3. Social service should follow up cases promptly on their return to the city, to prevent relapse which frequently occurs at the time; placing the patient in suitable occupation as soon as possible, to avoid the bad mental effect of being unemployed."

An element of social justice, not yet firmly established or, one might say, yet conceived of in most parts of our country, for the proper benefit of cardiac patients, is some form of compulsory disability insurance which will provide for financial help where employment is responsible for the development, or extension of cardiac disease, or death from it.

The probable relationship of cardiac infection to diseased tonsils is so firmly believed that we should consider our ability to meet the necessities of this situation. How many of the children of a city need to have their tonsils removed? According to Dr. Geo. Goler of Rochester, 2.6% of the total population, or 6.5%

of the children under 15, need tonsillectomy to save them from various direct and indirect results of infection through this portal of entry. In New York City, in 1920, a careful study, based on medical examination of school children, showed that about 55,000 children needed tonsillectomy. As a matter of fact, 46,273 operations for tonsillectomy were performed, and chiefly for children, in the hospitals and dispensaries of the city during 1920. It is believed that by proper central coördination, all tonsillectomies that are needed can be arranged for in existing facilities. Somewhere between 1% of the total population per annum estimated as needing tonsillectomy, in New York City, and the 2.6% considered to be in need of this treatment in Rochester, probably lies the truth of the situation. Possibly the reduction of tonsillar tissue and exclusion of infection from the cicatricial tissue by x-ray treatment, may simplify this problem. Similarly, the requirements and facilities for correction of oral sepsis should be studied and met. The present day inadequacy of prophylactic and curative dental care for old and young, is too well known to dwell upon here.

Why, then, do we say that the prevention of heart disease is a practical public health problem?

Because it is the cause of the greatest number of deaths and disabilities in the United States;

Because cardiac diseases fall within the class of preventable diseases, since their exciting causes, or infections, are severally communicable or preventable diseases, or both;

Because the individual has not the knowledge to, nor can he, control his life and environment, his schooling, treatment, employment or hazards of life alone, or escape by his unaided, individual efforts, the origin and development of these diseases.

Can we not expect that the extension of control of the water and milk supplies, the further reduction of the exanthemata, the infections of tonsils, teeth, and of the respiratory tract, will presently reduce the incidence of heart disease among the children of today so that the death rates of thirty and sixty years from infection will be reduced? Is it too much to believe what we have already seen, beginning in the past two years, the increasing vacancies in hospitals for care of the tuberculous, may with a hoped-for 50% reduction in this disease in the next thirty years, become so general that these sanatoria, for the most part ideally suited to, or easily adaptable for, the care of cardiac convalescents, will be turned into great salvage plants and training schools for the incipient, moderately advanced, arrested and active cases of cardiac diseases.

The reduction of typhoid has been so conspicuous and the permanence of its control so assured that we have a right to prophesy a reduction of that group of myocardial deaths shown to bear a direct relation to previous typhoid infection.

We do not know that syphilis has been reduced, but we believe this can be accomplished. We do know that scarlet fever, measles, pertussis and diphtheria are less frequent causes of death by 50-80%, than they were fifty years ago. It is suspected from some rather inconclusive hospital records that acute articular rheumatism has been reduced in recent years, and it is supposed that this is, in part, due to the removal of infected tonsils, the compulsory pasteurization of milk in our large cities, and the extension of oral hygiene, with its accompanying reduction of oral sepsis. (Dr. Alexander Lambert reports a reduction in admissions for acute rheumatic fever during the period 1907-1919, at Bellevue Hospital, from 2.45% of all hospital admissions to .52%.)

We see in the great incidence of cardiac diseases and deaths a token of our degree of failure in a crude, inconsistent and incomplete program of preventive medicine. These deaths and disabilities, represent the vouchers of our administrative stinginess, our policy of parsimony toward our health services. Even though we have no panacea or specific, we cannot be excused for letting the products of our carelessness march in an increasing army to the grave.

What is our professional answer, our program for action? First, we must make the possibility of prevention, prevention of infection, prevention of cardiac damage, prevention of extension of lesion or disability, and postponement of death from heart diseases, real to the practitioner of medicine.

As Dr. Thomas McCrae has well said:[1]

"The problem facing both general practitioner and consultant is to detect the persence of lesions in their early curable, or healable stage, and to recognize the first indications of

[1] Penn. Medical Journal, February, 1920, Vol. xxiii, p. 267.

failure of an established balance, reserve, or compensation."

All this means the introduction of a consciousness, a definite knowledge, and interest in the prevention of heart disease through medical education. We can no longer await the coming of patients in our offices, but must search for them among the presumably healthy and attack their disabilities before the patient is aware of them, and this through a development of a habit in the whole community to seek a thorough medical examination once a year for adults, twice a year for children under fourteen, and always after apparent recovery from any acute febrile disease.

We owe it to the great cardiac population of our country to release them from the traditional medical inhibitions, to encourage use instead of permitting atrophy. We owe the public intelligent warning of the seriousness of the rheumatic infections. The public owes us adequate provision of those institutional facilities we need for their care, and suitable training in self-support. Organized groups under medical leadership are necessary to develop the resources of our communities for the prevention and relief of heart disease.

The research problems that crowd upon us cover a wide field of laboratory sciences, medical practice and social economics, and involve the medical and associated professions. It is to be noted that public health and problems in prevention are subject to the same limitations which apply to the practice of personal medicine, namely, that treatment to be effective, or permanent in results, must be based on accurate diagnosis, and that communities differ almost as widely in their idiosyncrasies, their resources, their reaction to advice, as do individuals. No detailed recommendations, therefore, are offered for the remedy of the conditions of your respective communities based on diagnosis and treatment elsewhere, but may I hope that as you think over the symptoms and proofs of a widespread public disability which I have offered, you will search for the causes in your own environment and take an active part in the attack upon heart diseases with the determination characteristic of courageous and well informed physicians everywhere. Your Hippocratic oath requires this of you.

BIBLIOGRAPHY.

Reports of the Massachusetts General Hospital Social Service Department, Boston, 1911, 1918.

Reports of the Children's Heart Hospital of Boston, Mass. Annual since 1912.

The Trade School for Cardiac Convalescents Report, 1913-1914, 1914-1916.

Reports of the Bellevue Hospital Social Service Department, New York, N. Y., 1914.

Reports of the Peter Bent Brigham Hospital, Boston, Mass, 1915-1919.

Reports of the Burke Foundation, White Plains, N. Y., 1915, 1916, 1917-1918.

"Heart Disease and its Industrial Relations," Warren Coleman, M.D., American Journal of Public Health, 1915, vi, No. 5, 452.

"The Prevention and Relief of Heart Disease," Weekly Bulletin of the Department of Health of the City of New York, 1916, v, No. 37.

"Heart Disease in Infancy and Childhood," A. L. Goodman, M.D., Archives of Pediatrics, 1916, xxxiii, No. 12.

"Suggestions for Municipal Control of Carditis," Thomas B. Hegeman, M.D., Monthly Bulletin of the Department of Health of the City of New York, 1917, vii, No. 2.

"Recent Statistics of Heat Disease, with Special Reference to its Increased Incidence," Frederick L. Hoffman, Jour. A. M. A., 1920, lxxiv, No. 20, 1364.

"The Organized Care of Cardiac Children," William P. St. Lawrence, M.D., Hospital Social Service Quarterly, 1920, 11, 151.

"Heart Disease as a Public Health Problem," Lewis A. Conner, M.D., Jour. A. M. A., 1920, Vol. 74, No. 23, p. 1567.

"Effect of Tonsillectomy upon the Recurrence of Acute Rheumatic Fever and Chorea," William P. St. Lawrence, M.D., Jour. A. M. A., Oct. 16, 1920, Vol. 75, pp. 1035-1041.

First Report of "The Association for the Prevention and Relief of Heart Disease" (covering the period from its incorporation, Dec. 18, 1915, to Jan. 1, 1921).

"The Incidence of Acute Rheumatic Fever at Bellevue Hospital," Alexander Lambert, M.D., Jour. A. M. A., April 10, 1920, Vol. 74, pp. 993-995.

Reports of the Huddleston Memorial Class for Cardiac Disease in Children, by Charles Hendee Smith, M.D., Bellevue Pediatric Dispensary, 1917, 1918-1919.

"The Incidence of Heart Disease in Adults," by Louis I. Dublin, Ph.D., New York Medical Journal, April 10, 1920.

"The Treatment of Heart Disease by More and Longer Supervision," Robert H. Halsey, M.D., New York State Journal of Medicine, September, 1917.

"The Administration of Digitalis," T. Stuart Hart, M.D., New York Medical Journal, July 31, 1920.

"Employment for the Handicapped:" II, The Cardiac, Ida M. Duggan Hospital Social Service Quarterly, 1920, 11, 227.

"The Convalescent Treatment of Heart Disease by Exercise Applied through Natural Work and Play Methods," Frederic Brush, M.D., The Medical Record, Feb. 12, 1921.

"Clinic of Dr. T. Stuart Hart"—Presbyterian Hospital. "The Functional Activity of the Heart. Method of Classification," Medical Clinics of North America, March, 1921.

"Occupational Therapy in Heart Disease," Frederic Brush, M.D., The Modern Hospital, January, 1921, issue, Vol. xvi, No. 1.

"The Cardiac Clinic of Central Free Dispensary—Rush Medical College," Fred M. Smith, M.D., Hospital Social Service, June, 1921.

"Mary Zinn Home for Convalescent Children," Ernest P. Boas, M.D., Hospital Social Service, May, 1921.

"Social Treatment of Children with Cardiac Diseases of Children's Hospital, Boston, Mass.," Miss Mabel Wilson, Director, Social Service Department, Hospital Social Service, 1921, III, 2.

"Heart Affections in Relation to the Labor Market," R. O. Moon, M.D., F.R.C.P., British Medical Journal, May 8, 1920.

"Observations on the Nature and Symptoms of Cardiac Infection in Childhood." F. J. Poynton, M.D. Reprinted from British Medical Journal, March 2, April 13, July 6, and September 21, 1918.

"The Health of Food Handlers." A cooperative study by the Department of Health, the Metropolitan Life Insurance Company, and the American Museum of Safety. Report prepared by Louis I. Harris, M.D., and Louis I. Dublin, Ph.D., Monograph Series No. 17, Department of Health of the City of New York, August, 1917.

"Heart Disease in School Children," Charles Hendee Smith, M.D., "Mother and Child"—Vol. 2, No. 1, January, 1921. Published by American Child Hygiene Association.

"The Cardiac Clinic of Lenox Hill Hospital," Walter E. Bopp, M.D., Jour. A. M. A., Dec. 4, 1920, Vol. 75, pp. 1587, 1588.

"On the Value to the Community of Organized Effort for Control of Heart Disease," Lewis A. Conner, M.D. Read at stated meeting of College of Physicians, Philadelphia, May 4, 1921. (To be published.)

"Convalescent Institutions in the Care of Heart Disease." Read at stated meeting of College of Physicians, Philadelphia, May 4, 1921. (To be published.)

THE Manufacturers of Calox announce that liberal samples of Calox will be sent to any physician interested in becoming familiar with the product. Write: McKesson & Robbins, Inc., 91 Fulton Street, New York City.

Original Article.

THE ESSENTIAL FACTORS OF CANCER CAUSATION.

By James W. Shannon, M.B., San Diego, California.

(Continued from page 573.)

It is impossible to follow the course of water through the whole of the alimentary tract for the reason that, after leaving the stomach, it gradually becomes absorbed. We know, however, that it passes rapidly through the mouth, pharynx, and esophagus until it reaches the stomach, *where it is retained for a considerable time,* and that after leaving the stomach, there is no obstruction to its passage through the duodenum or other portions of the intestinal canal. The only important difference, therefore, between the stomach and the mouth, pharynx, esophagus, or duodenum is in the greater length of time during which water is retained therein, and it is for this reason only, and not because lesions are present more frequently in the stomach than in other parts, that gastric cancers outnumber cancers of all other abdominal organs together. The attack of cancer falls on the pyloric region because it is the most common seat of gastric lesions, but inasmuch as there is good reason to believe that lesions of the buccal cavity and of the duodenum are more frequent than in the pyloric region, we can hardly doubt that, if the opportunities for exposure of lesions in all these parts to water were equal, cancers of the mouth and duodenum would then outnumber cancers of the pylorus.

With regard to other parts of the alimentary system, our knowledge of lesions and of their exposure to water is insufficient to warrant our forming any conclusions. Nevertheless, if we believe that the principle of coöperation between lesions and water is true in the case of cancers of the mouth, stomach, and duodenum, we must also believe that it is true in the case of the intestines, peritoneum, liver, and other parts of the alimentary system lying beyond the range of observation. There is reason to think that cancer of the rectum is due, not to water which has passed through the alimentary canal, but to water deliberately applied in the course of the treatment for constipation and other affections.

Probably no organ or part of equal size is so frequently the seat of affections tending to result in lesions as the lungs, but notwithstanding this, there are few parts or organs in which lesions are better protected from water, or which show less tendency to become cancerous. The lungs, however, are not peculiar in this respect, since a brief consideration of the facts of cancer incidence as a whole will show that, whereas the greater proportion of the risks from cancer are borne by parts and organs which are commonly exposed to water, there is, in all parts and organs protected from such exposure, a remarkable freedom from the disease. It would be difficult to find a better illustration of this than that which is supplied by a comparison of the facts of cancer incidence upon the lungs and upon the stomach. Lesions are present more frequently in the lungs than in the stomach, and if "chronic irritation," or any other form of stimulus associated with their presence, were capable of causing cancer, we should certainly expect pulmonary cancers to outnumber gastric cancers. Since, however, the contrary is true, it is obvious that lesions acting alone cannot cause cancer, and it therefore becomes impossible to find a satisfactory explanation for the facts except on the ground that, whereas in the stomach exposure of lesions to water is almost continuous, the opportunity for such exposure can only arise in the lungs in the event of a rare accident.

Cancer of the female generative system stands second in order of frequency to cancer of the alimentary organs, not because it is more exposed to injurious influences or to water than many other parts of the body, but because of the vulnerability of one point, namely the cervix uteri. In so far as cancer is concerned, the cervix uteri stands in the same relation to the female generative system as the pyloric region does to the alimentary system, that is to say, it is the point upon which nearly the whole weight of the disease is focussed. It seems reasonable, therefore, to believe that the principles of causation which were found to be applicable to the problems of cancer in the alimentary system, will also serve to explain cancer of the female generative organs with the same degree of consistency.

The cervix uteri is, par excellence, the seat of inflammations, lacerations, ulcerations, erosions, and other lesions having a tendency to persist for months, or even years, and moreover, it is most favorably situated for contact with any water which may happen to enter the genital passages.

The female generative organs are not designed for the reception of water, and its presence in any part thereof must be regarded as abnormal; nevertheless, it is an exceedingly common event. Water may unintentionally enter the genital tract in the ordinary course of bathing, or it may be introduced deliberately as a routine measure of cleanliness, for purposes of medical treatment, and for other reasons. Having once gained an entrance, it is to be noticed: firstly, that owing to the absence of evaporation and to the impossibility of removing it by any ordinary means, it remains in contact with the mucous surfaces and with lesions which may be present thereon for an indefinite length of time, and, secondly, that women who are the subjects of female diseases in general, and of cervical lesions in particular, are more likely, both for reasons of treatment and of cleanliness, to resort to the use of water than those whose organs are healthy. Thus it happens that lesions actually invite the presence of water in the female genital tract.

Cancerous manifestations in the fundus uteri, ovary, and other parts of the female generative system are rare, not because of the absence of lesions therein, but because by their situation and structural design they are protected from contact with water. Theoretically, it is possible that water or the living organisms which it contains may enter the uterine cavity and even penetrate as far as the ovary, but, having regard to the fact that these parts can only accommodate a very small quantity of water, it is certain that, even under the most favorable circumstances, they can never be exposed to water, or to the causative agent of cancer on a scale comparable to that of the cervix uteri.

When regarded superficially it might seem that cancer of the mammary gland is a departure from the rule that cancers originate at the site of preëxisting lesions, but inasmuch as any difficulties which the subject may appear to present depend, not upon a deviation from the principles of cancer causation advocated herein, but upon the sense in which the terms, "site" and "lesion" are construed, they are more apparent than real. It was said in the foregoing that the rôle of lesions in the causation of cancer is that of a channel, passage, or gateway through which the causative agent of the disease is conveyed in water to the living cells of the tissues, and if the term, "lesion" is interpreted in this sense, all considerations concerning its physical character are immaterial. In so far, therefore, as the ducts of the mammary gland are capable of serving as a channel through which water and the living organisms contained therein may gain access to the cells of the mammary substance or to the cells of the ducts *themselves*, they may for the purpose of cancer causation be regarded as a lesion, regardless of whether they are diseased or healthy. The site of breast-cancer cannot be foretold with the same definiteness as in other cases; it may be any part of the duct or glandular tissues to which water happens to gain access.

The mammary ducts, fifteen to twenty in number, converge from all parts of the gland towards the summit of the nipple where they open on the surface. Having no valves or other controlling mechanism, they are unable to offer resistance to the passage of fluids in either direction. We may judge of the possibilities with regard to the passage of water from without inwards by the fact that during the period of lactation the flow of milk through them is independent of control. Under these circumstances, it is more than probable that in the course of bathing, either by aspiration, pressure, or capillary action, water is carried to the deeper parts of the gland. The changes which supervene upon the cessation of reproductive activity are calculated to increase the potency of the mammary ducts, and thus favor the entrance of water and the possibilities of cancer in the breasts of older women.

Independently of the foregoing considerations, there is indisputable evidence that mammary cancers result from exposure to water, but before it can be fully understood, it is necessary to become familiar with certain customs of the Japanese. The reputation of the Japanese for personal cleanliness is well known. A daily bath is a national custom scrupulously observed by all persons in every class of society; but it is important to notice that, with rare exceptions, the Japanese never bathe in cold water. The bath is prepared in the evening, and by a heating device is maintained at a temperature of 113° F. to 115° F. Beginning with the head of the family, the same water is used by each member of the household in succession, including guests and servants, so that often it requires several hours to complete the process.

(To be continued.)

THE BOSTON
Medical and Surgical Journal

Established in 1828

THURSDAY, JUNE 9, 1921

Published by The Massachusetts Medical Society under the jurisdiction of the following-named committee:

For three years HOMER GAGE, M.D., *Chairman*
EDWARD C. STREETER, M.D.
EDWARD W TAYLOR, M.D.
For two years WILLIAM H. ROBEY, JR., M.D.
ROGER I. LEE, M.D.
ROBERT B. OSGOOD, M.D.
For one year JAMES S. STONE, M.D.
HORACE D. ARNOLD, M.D.
CHANNING FROTHINGHAM, M.D.

EDITORIAL STAFF.

DAVID L. EDSALL, M.D.
WALTER B. CANNON, M.D.
REID HUNT, M.D.
ROBERT W. LOVETT, M.D.
EDWARD H. NICHOLS, M.D.
FRANCIS W. PEABODY, M.D.
JOHN P. SUTHERLAND, M.D.
S. BURT WOLBACH, M.D.
GEORGE R. MINOT, M.D.

WALTER P. BOWERS, M.D., *Managing Editor*
GEORGE G. SMITH, M.D., *Assistant Editor*

SUBSCRIPTION TERMS: *$6.00 per year, in advance, postage paid for the United States, $7.56 per year for all foreign countries belonging to the Postal Union*

Material for early publication should be received not later than noon on Saturday. Orders for reprints must be sent to the printer with galley proof of paper. Upon written request, authors will be furnished free one hundred eight-page reprints, without covers, or the equivalent in pages in articles of greater length.

The Journal does not hold itself responsible for statements made by any contributor.

Communications should be addressed to The Boston Medical and Surgical Journal, 126 Massachusetts Ave., Boston, Mass.

MUTUAL INSURANCE FOR PHYSICIANS.

THERE seems to be an increasing tendency to sue physicians for alleged malpractice. This inclination may be based on honest conviction that a doctor has been careless or unskillful, a desire to extort money, the suggestion of friends, or advice of attorneys. Medical practitioners are not always businesslike in recording facts and, as a rule, do not impress juries favorably by testimony on the witness stand, hence are sometimes victimized by force of circumstances. It is generally recognized that evidence of disability, or suffering, arouses sympathy in the minds of jurors, and the workings of untrained intellects do not always lead to logical conclusions. It must also be recognized that a proportion of the people respond to arguments designed to discredit the practice of medicine. The increasing number of suits, with the necessity for defence or compromise, has led some insurance companies to publish notices which announce the intention to increase rates. Physicians are already burdened by various forms of licenses, greater cost of transportation, taxation of income and many minor items; hence any method of coöperation which may tend to reduce expenses is pertinent.

A plan to form a mutual insurance company with membership confined to members of the Society, has been considered, legal advice obtained and some details formulated. A company of this sort cannot legally do business unless it is incorporated according to Massachusetts laws. The only serious obstacle is the initial expense, for the law requires that paid up premiums amounting to fifty thousand dollars ($50,000) must be secured before functioning as an insurance company. This is not insurmountable, for a mutual company can pay back in dividends a substantial proportion of its unused income after providing for a reserve fund.

The JOURNAL office will be placed at the disposal of a company if physicians are interested and decide to incorporate it. By this plan, the JOURNAL would provide all the bookkeeping, receive payments and deposit funds under the direction of the corporation. If the officers would be willing to serve without salaries, the only expense would be for a part-time clerk, unless the business should develop into larger proportions than now seems probable. There would be no charge for rent or salaries, and the Editor of the JOURNAL would give bonds to protect the company against possible loss. Under these plans there would be no overhead expense, which contributes largely to the cost of insurance by companies organized for profit, or for the purpose of furnishing employment for officials.

The same auditor now employed by the Massachusetts Medical Society could examine the details of financial transactions and report to the company at less expense than would be the case for an independent organization. This company need only meet the expense of actual damages awarded, if any, as a result of any suit, for the Society now provides legal defence and, if the company should elect to have its members take advantage of the Medical Defence Act, another large item of overhead expense in insurance business would be eliminated.

If members of the Society are interested in discussing this plan, the JOURNAL would make all announcements and preliminary arrangements, provide for meetings, employ counsel necessary in securing a charter and serve the members of the Society in any way which may be desired.

There are now nearly four thousand mem-

bers, a large proportion of whom carry liability insurance.

A board of managers could pass upon questions relating to any suit, and decide upon the course to be pursued after conference with counsel provided by the Society.

It has often been suggested that physicians may have to organize for defence against various matters affecting the profession. Here is an opportunity for testing the advisability of organization in a matter of common interest.

NARCOTIC REGISTRANTS MUST RE-REGISTER THIS MONTH.

The Internal Revenue Office is paying narcotic registrants its annual call again, to remind them that they must re-register on or before July 1, if they intend to continue handling or prescribing narcotic drugs for the period July 1, 1921, to June 30, 1922.

Practitioners, hospitals, sanatoriums and educational institutions, which constitute Class 4 of the Revenue Department's classification of registrants, have been mailed proper forms to be filled out and returned to Collector John J. Mitchell with payment of $3.00, the annual amount of tax, prior to the beginning of the period. To avoid the penalty imposed upon 1500 delinquents a year ago, they will execute the forms promptly.

Slight misunderstanding of the requirements of the Harrison Narcotic Law and amendments has arisen among practitioners, who believe they do not have to register with the Internal Revenue Office if they do not actually handle or dispense narcotics. The department has ruled that although he does not actually dispense, a physician must be registered if he wishes only to prescribe narcotics, as the registration number must be on all these prescriptions. This misunderstanding was the result of many penalties being imposed last year.

Persons desiring to discontinue handling narcotic drugs after July 1, should notify the Internal Revenue Office prior to that date so that proper steps can be taken legally to terminate the business, return all unused forms and have registration numbers cancelled. Should any person go out of business and not notify the Revenue Department, he will be carried on the bureau's records under his original registration number, and after July 1, this will cause him to be classified as a delinquent.

Instructions sent out with the forms this year call attention to the important fact that all registrants in Classes 1, 2, 3, and 4, must also register in Class 5 in order to dispense or deal in exempt preparations, although this additional registration does not require any further payment of tax.

They are also reminded that persons registering in Classes 3 (retail dealers) and 4 must prepare, under oath or affirmation, a duplicate inventory of all non-exempt narcotic drugs and preparations in their possession on the date of application, or submit an inventory of any date between the previous December 31 and the date of application when they register.

MEDICAL NOTES.

Rural Health and Medical Service.—Minutes of meeting for organization of Committee for Rural Health and Medical Service, held in Boston, Friday, April 29th, at 11 A.M., in the office of Dr. Kelley, Commissioner of Health.

Those present were: Dr. E. R. Kelley, Commissioner of Health; Mrs. William Lowell Putnam, of Woman's Municipal League; Dr. E. H. Bigelow, Chairman Public Health Committee of the Massachusetts Medical Society; Mr. Leslie R. Smith, Master of the State Grange, representing Commissioner of Agriculture A. W. Gilbert; Dean E. M. Lewis, representing President K. L. Butterfield of the Massachusetts Agricultural College; P. W. Goldsbury, and Prof. Walter B. Cannon of the Harvard Medical School and member of the American Medical Association Council on Public Health and Instruction.

Prof. E. M. Lewis was elected temporary chairman. The following permanent officers were elected: President, Kenyon L. Butterfield of Amherst; Vice-Presidents, Dr. Eugene R. Kelley of Boston and Dr. Walter B. Cannon of Cambridge; Secretary, Dr. Paul W. Goldsbury of Deerfield.

Dr. Goldsbury reported having gone about Franklin County, visiting some twelve towns. Four of these trips were made with the Farm Bureau team, and he had had an opportunity to meet groups of people and speak briefly of plans for advance of health conditions. He had had more or less extended interviews with some 24 physicians in regard to their own problems and sounded them out with reference to the building up of a more unified clinic in Greenfield

as a Centre. This clinic to include, at the first, tubercular, mental and venereal disease cases and, possibly, orthopedic cases. He described a number of these towns, how they were situated in reference to good roads, railroad lines of travel, and how they were manned by physicians, thus illustrating a need for better hospital facilities and an extension of clinical education. He also spoke of the interest that leading medical men in Boston had shown toward giving services to inaugurate such clinics at a distance from Boston. He emphasized the fact that the extension of the Home Economics work of the Farm Bureau coming up, as it did now, to the subject of nutrition, school lunch problems, etc., and the pretentious plans of social service agencies—Red Cross Society, the Public Health Associations for district and county nurses, warranted better unification of the interests of the physicians and such organization as would keep them abreast of all these advances.

Dr. Cannon has been a member of the Council of American Medical Association on Public Health and Instruction since such council was organized. He told of the work organized and developed by Dr. F. E. Sampson of Creston, Iowa, and now carried along by the Greater Community Hospital Association, which affords hospital facilities to a group of counties about, and which is designed to "promote interest and activity through auxiliary associations and societies or otherwise, throughout the neighboring communities in measures tending to conserve the public health and prevent disease and disability." The work has been a basis for modelling permissive legislation in some 20 states. Dr. Cannon hoped the Committee could meet Dr. Sampson when he would be in Boston June 6-10, at the sessions of the American Medical Association.

Committee on Rural Health and Medical Service.

The "country" is the natural playground of health. Conditions should be provided to insure there all the comforts and advantages of modern life and its individual and social efficiency.

Objects.

To bring together all agencies devoted to rural welfare.

To promote cordial coöperation between the older and newer agencies so engaged.

To assure the highest usefulness of the country physician who gives of his best strength and service to the maintenance of the life, health, and welfare of the community. The family doctor has been a home and individual stabilizer. In the general practice of medicine, there exists an unusual opportunity to minister to the sanctity of the home, the integrity of family life, and to a protection of the individual's private interest, and in the rural field where the doctor is placed, he renders invaluable aid, not only professionally, but with his intimate knowledge, training, and experience with the human constitution and fabric, he is especially fitted to uphold the social life of the community and maintain its fullest integrity. Medical service must be given support in the way of modern comforts and equipment, conveniences, good roads, etc., all of which has an effect upon the stimulus and circulation of individual and community life.

To make such personal acquaintance with each field as will attract and encourage the support and active coöperation of all local agencies and leaders.

To help to bring to rural and needy sections better hospital advantages.

To endeavor to provide better educational and clinical facilities necessary for attracting and retaining men of competent professional ability to serve such districts.

Committee:

Dr. E. R. Kelley, Commissioner of Health, Boston; Prof. Walter B. Cannon of Harvard Medical School, and member of Council on Health and Public Instruction of American Medical Association, Cambridge; Dr. K. L. Butterfield, President Massachusetts Agricultural College, Amherst; Dr. Arthur W. Gilbert, Commissioner of Agriculture, Belmont; Dr. Payson Smith, Commissioner of Education, Boston; Dr. Alfred Worcester, President Massachusetts Medical Society, Waltham; Dr. E. H. Bigelow, Chairman Public Health Commission of the Massachusetts Medical Society, Framingham; Dr. G. H. Wright, Harvard Dental School, Brookline; Mrs. William Lowell Putnam, Boston; Dr. Paul W. Goldsbury, Deerfield.

The statement of the general purposes of the organization as outlined by Dr. Goldsbury, was discussed and was accepted, with the elimination of a minor paragraph.

Matters relating to the promotion of the work, and especially to ways and means of

financing it were discussed. The opinion was expressed that counties and districts most to be benefited should be solicited, as far as possible, to bear the burden of expense associated with the work and that societies and associations should be interested to have the work presented to them and appeals made for its support.

A finance committee was appointed: Mrs. William Lowell Putnam, chairman; Pres. K. L. Butterfield and Dr. E. H. Bigelow. The matter of finding a man who could give time and interest essential to act as treasurer, was brought up. Meeting was adjourned.

PAUL W. GOLDSBURY, *Secretary.*

Since notification to President Butterfield of his selection as President, I have received the following from him, dated Amherst, May 7, 1921:

"My dear Dr. Goldsbury:—I want to help in the scheme proposed, but I can't accept the chairmanship of the committee. I have pledged myself, already, to all the work outside the administration of the college that I can possibly carry in justice to the college and myself, as well as the schemes undertaken. Somebody else must act as chairman. Yours very truly, (Signed) Kenyon L. Butterfield."

Since our meeting, also, communication has been had with Dr. F. E. Sampson of Creston, Iowa, and our next meeting will be planned during the week of the meeting of the American Medical Association, June 6-10, with a view to meeting with Dr. Sampson and taking up certain few important matters. Card will be sent out as to time and place of meeting, later.

PAUL W. GOLDSBURY, *Secretary.*
Deerfield, May 17, 1921.

MME. CURIE'S FIRST AMERICAN CONTRIBUTION.—The July issue of the *Medical Review of Reviews* will contain a lengthy original contribution by Mme. Curie entitled "The Radio Elements and Their Applications." It is, we believe, the first and only contribution which this noted scientist has made to an American publication, and is extremely valuable. A copy of the July issue containing it will be sent gratis to any physician making the request.

Address, *The Medical Review of Reviews*, 51 East 59th Street, New York.

A HANDY LITTLE REFERENCE BOOK.—Parke, Davis & Company recently issued a little reference book on Adrenalin that is conveniently arranged for ready consultation.

Adrenalin is the original natural preparation of the active principle of the suprarenal gland. It is a vastly better product than any synthetic compound, and under the present highly perfected process of manufacture it is a stable and dependable preparation of uniform strength.

NOTES FROM DISTRICT SOCIETIES.

DR. EDWARD W. BARTOL has recently located in Lancaster to take the practice of the late Dr. Chester C. Beckley. Dr. Bartol has been elected to the Staff of the Clinton Hospital.

DR. EDWARD B. BIGELOW has resigned from his position as Supervisor of the Medical Service at the Worcester City Hospital and has accepted the position as Assistant Medical Director of the State Mutual Life Assurance Company. He retains his position as Visiting Physician to the Worcester City Hospital.

DR. F. E. GARLAND, for the Health Committee of the Massachusetts State Medical Society, has been at the Worcester City Hospital during the past week, demonstrating the Schick Test. This is a part of a state-wide campaign undertaken by the committee to introduce this method of reducing the mortality in the state from diphtheria.

DR. HOMER GAGE has been recently elected president of the Worcester Welfare Association.

HAMPDEN DISTRICT.—The Springfield Academy of Medicine held a special meeting Tuesday, May 24, 1921, and passed the following resolution: "We, the members of the Springfield Academy of Medicine, are familiar with the medical needs of this city, and hence are convinced that there is at the present time no need for a free medical dispensary. However, should future development reveal the need of some such agency, we are convinced that from the viewpoint both of public health and of civic economy, existing institutions should be utilized, rather than that an expensive duplication of plant and equipment be made an added charge upon the community."

The Junior Chamber of Commerce, the energetic offspring of the Springfield Chamber of Commerce, has been, with all the enthusiasm of youth, for some time agitating the opening

of a free medical dispensary in Springfield. The agitation succeeded in eliciting the support of enough philanthropic individuals and charitable institutions to warrant a rather formidable organization of Junior Chamber of Commerce members bent on establishing such an institution. A definite plan was publicly presented, with estimates of the probable initial expense and annual cost of maintainance. A circular letter was sent to every physician in the city, soliciting not only approval of the project, but gratuitous service in the dispensary as well. A few favorable replies were received, but for the most part, physicians simply dropped the appeal in the waste basket. Much was publicly made, however of those few favorable replies, and the Junior Chamber of Commerce was about to go to the public for funds. This contemplated action brought about the special meeting of the Springfield Academy of Medicine, with results as stated. At the same time, the Directors of the Community Chest which collects and disburses funds for all the well organized and well conducted charities in the city, issued, after careful consideration, the statement that they did not endorse the project for a free medical dispensary, because they deemed it at present, extremely ill-advised. The agitation will probably, therefore, for the time being, be abandoned. Eventually, when the times are more propitious and when the need for such an institution is more clearly demonstrated, a compromise can be effected whereby the need will be met by establishing such an agency in connection with an already existing charity.

ALLEN G. RICE.

BOSTON AND MASSACHUSETTS.

NEW ENGLAND SURGICAL SOCIETY.—The next meeting of the New England Surgical Association will be held at Worcester, Massachusetts, on September 21 and 22, 1921. Headquarters, Hotel Bancroft. There will be clinics at the Worcester City Hospital, Memorial Hospital, and St. Vincent's Hospital on the morning of September 21st. After the reading of papers during the afternoon session, Doctor and Mrs. Homer Gage will entertain the members at tea at Shrewsbury. The second day will be devoted to a continuation of the scientific program. Members are invited to present contributions of their own selection, and are requested to notify the Secretary promptly, in order that the program may be completed as early as possible. The time allowed for the reading of papers shall be fifteen minutes, and five minutes for each speaker during the discussion, excepting invited guests. Members are requested to notify the Secretary, P. E. Truesdale, 151 Rock Street, Fall River, Mass., if lantern slides are to be shown.

WEEK'S DEATH RATE IN BOSTON.—During the week ending May 21, 1921, the number of deaths reported was 193 agaisst 239 last year, with a rate of 13.29 against 15.42 last year. There were 29 deaths under one year of age against 43 last year.

The number of cases of principal reportable diseases were: Diphtheria, 72; scarlet fever, 51; measles, 100; whooping cough, 15; typhoid fever, 5; tuberculosis, 54.

Included in the above, were the following cases of non-residents: Diphtheria, 9; scarlet fever, 4; measles, 1; whooping cough, 1; typhoid fever, 2; tuberculosis, 11.

Total deaths from these diseases were: Diphtheria, 5; scarlet fever, 2; measles, 1; tuberculosis, 13.

Included in the above, were the following cases of non-residents: Diphtheria, 3; tuberculosis, 2.

NOTICES.

DURING THE A. M. A. CONVENTION the Medical School Building and Laboratories of Tufts College, located at 416 Huntington Avenue, will be open for inspection from 9 A.M. to 4 P.M. There will be exhibits of experimental work on focal infections in the Pathological Laboratory. The Departments of Physiology, Biological Chemistry and Histology will also present interesting material. A survey of the distribution of the graduates of medical schools, as affected by the attractions of urban *vs.* rural centres, will be shown.

LECTURE COURSES WITH CLINICS for teachers, nurses, and physicians, relating to speech correction and development, will begin at the Northwestern University Summer School, June 27 and July 25, 1921. For particulars apply to Walter B. Swift, M.D., 110 Bay State Road, Boston

RECENT DEATH.

DR. LE GRAND BLAKE, a Fellow of the Massachusetts Medical Society, died at his home, Riverside, R. I., April 22, 1921, aged 67 years. He was a graduate of Tufts Medical School in 1894.

LOESER'S INTRAVENOUS SOLUTIONS

are not "cures"

They are simple solutions of U. S. P. and standard salts with the exact contents plainly stated on the label.

Repeated sterilization during manufacture and careful sterilization at twenty-pound steam pressure of the filled and sealed ampoules, assure absolute aseptic solutions.

Animal experiments and control tests are continually carried on to determine toxicity, and check solutions.

Write for "Journal of Intravenous Therapy," Price List, Clinical Reports, Reprints, etc.

New York Intravenous Laboratory
112 West 21st Street, New York

ARSPHENAMINE ("606")
and
NEOARSPHENAMINE ("914")

Our arsphenamine and neoarsphenamine have achieved an enviable reputation. Our large research staff is constantly at work upon the elaboration of the least toxic and most therapeutically active compounds. **Our laboratories are not in any sense conducted for private gain**, and we can, therefore, afford to devote our proceeds to research in chemotherapy.

The value of neoarsphenamine is directly related to two factors—its toxicity and its therapeutic effect. **The toxicity of neoarsphenamine can be reduced to such an extent that it will pass at figures far beyond the Government requirements**; as a rule, these products will have a lower therapeutic effect. **THE BEST PRODUCT IS THE ONE POSSESSING THE HIGHEST CHEMOTHERAPEUTIC INDEX.** (i.e., the ratio of the maximum tolerated to the curative dose). **THIS DESIDERATUM IS OUR CONSTANT AIM.**

DERMATOLOGICAL RESEARCH INSTITUTE, Inc.
1720 Lombard St. and 1713-23 Naudain St.
Philadelphia, Pa.

A SMALL HOME SCHOOL

In the pine woods, for delicate or young children. Care of Trained Nurse. Excellent teaching. Outdoor life. Apply to
Rev. Mother, O. S. A.
St. Anne's House
44 Temple St., Boston, Mass.
2-tf,B363

TO LET AT 74 BAY STATE ROAD

Single and double offices for doctors.
11-tf,B401

PRACTICE FOR SALE

Unusual opportunity for a good man to take general practice. Established ten years, last year collected $6,000. Have a desirable home to go with practice if desired. Price of home, $10,000; practice, $1,500. Would stay and introduce. I wish to specialize. Address
A291, Care of
Boston Medical and Surgical Journal
17-tf

900 BEACON ST.

To rent, entire second floor for doctor's office, with privilege of living in same.
10-tf,B390

WANTED

Male assistant resident physician. Female assistant resident physician. Permanent positions. Good chance for advancement. Suitable accommodations for those who are married. State Hospital in Massachusetts. Address
A297, Care of
Boston Medical and Surgical Journal
21-4t

WANTED

Assistant physician at the Bridgewater State Hospital. Previous experience with insane unnecessary, but general medical training essential. Good opening for unmarried man. Compensation includes salary, board, room and laundry. Apply F. H. CARLISLE, M.D., Medical Director
Bridgewater State Hospital,
State Farm, Mass. 21-4t,B409

WANTED

Woman physician at Connecticut State Farm for Women at Niantic, Conn. For information address
Ida M.S. Thompson, Secretary
190 Retreat Ave., Hartford, Conn.
20-4

WANTED

Male assistant physician to fill vacancy on medical staff of the State Hospital for Mental Diseases, Howard, R. I. Address
Arthur H. Harrington, M.D., Supt.
20-tf,B407

OFFICE TO SHARE

Having a well equipped office at 353 Commonwealth Ave., I would like to share it, for the morning or late afternoon hours, with some other physician.
Dr. GEORGE ELISHA MAY
Phone, Back Bay 9800
18-tf B403

OFFICES FOR DOCTORS AND DENTISTS

238 Newbury St. Unusual facilities offered. Telephone B. B. 84.
22-tf-B417

TO LET

Front office at 375 Commonwealth Ave., in doctors' building, opposite Harvard Club. Continuous hot and cold water, with use of laboratory, if desired. A physician with morning office hours preferred. Telephone service continuous.
Telephone B. B. 8755
21-tf,B414

TO LET

Physician's office, 430 Marlborough St. Large front room, heat, light and telephone attendance. Telephone B. B. 1878.
21-1t,B413

DOCTOR WANTED

To take charge of plant hospital at large mill in Massachusetts, on salary basis. A splendid opportunity for a man who has had experience in handling industrial accidents and who is able to take care of his own surgical cases. State age, training and experience. Address
A299, are of
Boston Medical and Surgical Journal
22 4t

WANTED

Position as part time assistant to busy surgeon, gynecologist or obstetrician by young, energetic physician. Graduate of Class A school, extensive training, good appearance and address. Excellent references. Address
A300, Care of
Boston Medical and Surgical Journal
22-2t

SANITARIUM OR HOSPITAL

Called the South Shore Hospital, for sale. Located at Marshfield Hills, 40 rooms furnished for hospital purposes, together with 15 acres of land. On state road to Plymouth. Price $25,000. Apply to
CHARLES E. FITZ
50 State St., Boston
Tel. Main 2477 22-tf-B408

FOR SALE

Vetz Surgical Chair. Telephone Malden 27.
22-tf,B415

A BUSINESS OPPORTUNITY

FOR RENT OR SALE, first-class Hydro-Therapeutic and Turkish Bath Establishment of 24 rooms, electric light cabinets, vapor baths, and swimming pool. Established 10 years. Centrally located in Boston. At present in active operation with competent attendants. Good reason for selling. Address
A301, Care of
Boston Medical and Surgical Journal
22-4t

ASSISTANT

After eight years' general practice in Boston suburbs, male, age 33, wishes to form connection with a Boston man who wishes capable assistant for good internal medicine, upon basis of either salary or commission References upon application. A302, care of Boston Medical and Surgical Journal. 23-2t
21-tf,B41

VICTORY KNOLL CAMP
Moody Mountain Maine
For children under 14 years.
Endorsed by leading Surgeons and Physicians. All sports, tutoring, hiking, trips. Attending Physician. Resident Nurses. Councilors all leaders. References required. Send for illustrated catalogue. Until June 1st, address
THE MISSES GEARON
839 Boylston Street, Boston, Mass.
17-8

W.S.S.
WAR SAVINGS STAMPS ISSUED BY THE UNITED STATES GOVERNMENT

W.S.S.
WAR SAVINGS STAMPS ISSUED BY THE UNITED STATES GOVERNMENT

WAPPLER
ELECTRO-MEDICAL APPARATUS
CYSTOSCOPES, URETHROSCOPES,
PROCTOSCOPES, AURISCOPES,
OPHTHALMOSCOPES
And Other Electric Lighted Instruments
REPAIRING, LAMPS FITTED AND SUPPLIED
CHAS. H. KEHLENBACH, 1074 Boylston Street
SALES AGENT BOSTON, MASS.
TEL. BACK BAY 8116

PHYSICIANS MUST HAVE DEPENDABLE TRANSPORTATION
THE STEARNS KNIGHT CAR
Can be relied on under all conditions.
The engine and chassis represent the best type of automobile construction.
Apply for demonstration to
J. H. MacALMAN, 100 Massachusetts Ave.
(Mention the Boston Medical and Surgical Journal)

Write For Catalog
"When you need Auto Supplies
See
John & Arthur"
"Everything for the Automobile"
169 Mass. Ave. Boston, Mass.
John J. Mahoney, Pres. Treas. Tel. B. B. 6363

CHARLES B. TOWNS HOSPITAL

For definite hospital treatment of toxic addictions and their sequelae, including those resulting from use of drugs, alcohol and tobacco, as well as toxemias arising from morbid processes such as under-oxidation, faulty metabolism, etc. Physicians are invited to accompany the patient and supervise definite medication and physical after-care.

Situated directly across from Central Park. Provided with every useful facility for hydro- and electro-therapy. Outdoor exercises and physical training under competent director. Utmost privacy if desired. Definite fee charge fixed in advance for all services. Correspondence invited. Literature on professional request.

CHARLES B. TOWNS HOSPITAL, 293 Central Park West, New York City

BOURNEWOOD HOSPITAL

SOUTH STREET, BROOKLINE, MASS.

Established 1884

For a limited number of cases of Mental and Nervous Disease only
Post Office, Chestnut Hill. Telephone, "Parkway" 300
Nearest station, Bellevue, N.Y., N.H., & H. R.R.

GEORGE H. TORNEY, M.D.
Physician in Charge

HENRY R. STEDMAN, M.D.
Consultant

CHANNING SANITARIUM, Inc.

Wellesley Avenue, Wellesley, Mass.

(Established in Brookline, 1879. Transferred to Wellesley, 1916.)

Seven new buildings on fifty acres of high woodland. Sleeping porch and private bath for each patient. Large and small suite cottages. Separate buildings for men and women. Facilities for occupation and diversion. Complete equipment for Vichy, Nauheim and electric baths and other forms of hydrotherapy. Alpine lamp for heliotherapy.

Especially designed and equipped for the care and treatment of nervous cases.

DONALD GREGG, M.D. WALTER CHANNING, M.D.

Professional Cards

RING SANATORIUM
AND
HOSPITAL
Inc.

Arlington Heights, Massachusetts

Eight Miles from Boston
Telephone, Arlington 81

For Chronic, Nervous and Mild Mental Illnesses. Five separate houses permit of segregation and a variety of accommodations.

Boston Office—By appointment
496 Commonwealth Ave.
Telephone, Back Bay 8774
ARTHUR H. RING, M.D.,
Superintendent.

Dr. Mellus' Private Hospital
FOR MENTAL DISEASES

419 Waverley Avenue, Newton, Mass.
Reached by train to Newton, or by electric cars *via* Commonwealth Avenue to Grant Avenue.
Edward Mellus, M.D.

DR. TAYLOR'S PRIVATE HOSPITAL
For the Treatment of
NERVOUS DISEASES
ALCOHOLISM AND DRUG ADDICTIONS

House newly equipped and furnished, skilled attendants, good food, and comfortable rooms at moderate rates.

Methods of treatment are those proved best after 17 years' successful experience.

FREDERICK L. TAYLOR, M.D.
45 Centre Street, Boston
(Near Eliot Square) (Roxbury District)

MRS. SPINNEY'S HOUSE
A restful home for invalids and elderly persons, especially for the building up of convalescents amid attractive surroundings. Spacious piazzas, well stocked library, trained attendants.

MARY E. H. SPINNEY
17 Parley Vale, Jamaica Plain, Mass.
Tel. Jamaica 2280

"BELLEVUE"
Superior homelike accommodations for five patients. Nervous and Mild Mental Disease, selected cases of Alcoholism, and Elderly Women for whom medical supervision is desired, are received.

MARY W. L. JOHNSON, M.D.
158 WALCOTT ROAD, CHESTNUT HILL, MASS.
Telephone, Brookline 5381-W

WOODLAWN SANITARIUM
FOR THE CARE OF EPILEPTICS
DR. H. W. HAMMOND, *Supt.*
WEST NEWTON, MASS.
tf

Wiswall Sanatorium
Inc.
A Sanatorium for the Treatment of Nervous and Mental Diseases

New Buildings, every facility for comfort; in midst of twelve acres of high land, covered with beautiful oak and pine trees, fully equipped for hydrotherapeutic and electrical treatment.

H. O. SPALDING, M.D.,
Superintendent
E. H. WISWALL, M.D.,
Asst. Physician
Wellesley, Mass.
Telephone, Wellesley 261

DR. GIVENS' SANITARIUM
(THE STAMFORD HALL COMPANY)
STAMFORD, CONN.

For the scientific treatment of Nervous and Mental diseases, Drug and Alcoholic addictions, and General Invalidism. Completely equipped for the care and comfort of patients—Hydro-Therapy, Electro-Therapy, Massage, Occupational Therapy and Amusements.

Located in a beautiful natural park of 100 acres, with numerous detached buildings, insuring privacy.

Fifty minutes from New York City on the New Haven Railroad.

Address
Frank W. Robertson, M.D., Pres. and Med. Dir.
Phone, 70 Stamford
New York City Office: 412 West End Ave.
Monday, Wednesday, and Friday at noon.

WOODSIDE COTTAGES
FRAMINGHAM, MASSACHUSETTS
BOSTON OFFICE, 178 COMMONWEALTH AVE.
TEL. BACK BAY 808

A small sanitarium, pleasantly located on high ground, especially adapted to the care of chronic invalidism, rest cases, convalescents, and the aged. Separate groups. Committed cases not received.
Tel. Framingham 26.
FRANK W. PATCH, M.D

GLENSIDE
For Nervous and Mental Diseases
6 Parley Vale,
Jamaica Plain, Mass.
MABEL D. ORDWAY, M.D.
Telephone, Jamaica 44.

HERBERT HALL HOSPITAL, Inc.
WORCESTER, MASS. Established in 1872



A Hospital for the Care and Treatment of those afflicted with the various forms of Nervous and Mental Diseases. Accommodations for a few chronic quiet patients at special rates.

WALTER C. HAVILAND, M.D., *Superintendent*
H. LINCOLN CHASE, M.D., *Resident Physician*

THE MILLET SANATORIUM FOR TUBERCULOSIS
EAST BRIDGEWATER, MASSACHUSETTS
C. S. MILLET, M.D., MEDICAL DIRECTOR

The Boston office of the Millet Sanatorium, East Bridgewater, Massachusetts, has been removed to
45 BAY STATE ROAD
Dr. Millet may be seen at this office on Tuesdays and Fridays between the hours of 11 and 1 o'clock.

A Relief for Chronic Constipation
During Pregnancy
For Nursing Mothers

FRUTOSEN
The Laxative
Par Excellence
For Children
Palatable No Griping
In 4-ounce bottles

FRUTOSEN DRUG CO.
Boston, Mass.

TUFTS COLLEGE MEDICAL AND DENTAL SCHOOLS

The Tufts College Medical School offers a four-year course leading to the degree of Doctor of Medicine. The next session begins September 19, 1921. Students of both sexes are admitted upon presentation of an approved high school certificate and, in addition, college credit indicating two years' work in Chemistry, English, Physics, Biology, and French or German.

Beginning January, 1921, all candidates for admission to the Tufts College Dental School must present evidence of having attended one year in a recognized college or university, and to have passed the subjects of the year. These subjects must include Physics, Chemistry, Biology and English.

Tufts College has arranged a One-Year Pre-Dental Course which fulfills these requirements. A special bulletin describing the course will be sent upon application.

CHARLES F. PAINTER, M.D., *Dean.* WILLIAM RICE, D.M.D., *Dean.*

For further information, apply to FRANK E. HASKINS, M. D., *Secretary*, 416 Huntington Avenue, Boston 17, Mass.

THE NEW YORK EYE AND EAR INFIRMARY

School of Ophthalmology and Otology

For Graduates of Medicine

Clinics daily by the Surgical Staff of the Infirmary. Special courses in Ophthalmology, Refraction, Operative Surgery of the Eye and Ear, Pathology and External Diseases of the Eye.

The abundant clinical material of this well-known institution affords students an unusual opportunity for obtaining a practical knowledge of these special subjects. Two vacancies in the House Staff exist in March, July, and November of each year. For particulars address the Secretary,

DR. GEORGE S. DIXON, NEW YORK EYE AND EAR INFIRMARY.

HARVARD DENTAL SCHOOL

BOSTON, MASS.

A department of Harvard University

Send for Announcement

A four-years' course

DR. EUGENE H. SMITH, *Dean*

BOSTON UNIVERSITY SCHOOL OF MEDICINE

Founded 1873 Reorganized 1918 Class A

ENTRANCE REQUIREMENTS

A minimum of two college years including Chemistry, Physics, Biology and in addition to English, at least one foreign language.
Men and women admitted upon equal terms.
Students limited to 200.
Students admitted to advanced standing.

INSTRUCTION

All fundamental medical sciences in charge of full-time professors and assistants. Abundant laboratory facilities.

CLINICAL TRAINING

Unusually extensive facilities provided in an approved hospital having 559 beds, with departments of research, neurology, obstetrics, medicine and surgery, specialties, contagious, pediatrics, venereal diseases. All departments except contagious are located within two minutes walk of college.
Ward walks, clinical clerking, pathological conferences, large Out-Patient Department.
Students also receive instruction in Boston City Hospital and Westboro State Hospital for Insane.
Further information and catalog furnished on application to
EDWARD E. ALLEN, M.D., Registrar, 80 E. Concord St., Boston, Mass.

GRAND VIEW SANITARIUM AND HOSPITAL

547 Central Street, Winchendon, Mass.

A Modern Health Resort for Convalescent Cases, Semi-Invalids, and General Medical and Surgical Work. Beautifully located with views of Monadnock in the north and Wachusett in the south. Pine grove. Rates moderate.

Licensed Lying-in Hospital. Confinements a specialty.

Doctors' private patients will receive our special care.

Write for particulars.

Julia A. Nason, R.N., Supt. **Howard N. Nason, M.D.,** Physician

BOSTON NURSES' CLUB, Inc., AND REGISTRY

839 BOYLSTON ST., BOSTON, MASS.

BACK BAY 8787

SWITCHBOARD WITH TWO TRUNK LINES

Graduate Nurse in attendance day and night.

Graduates, Undergraduates, Attendants, Hourly Nursing, Masseurs, Male Nurses.

MISS FLORA E. ROSS, R.N., REGISTRAR

WET NURSES NEEDED

to fill increased demand at

WET NURSE DIRECTORY

Under the direction and control of the Infants' Hospital. Wet nurses may be obtained by telephoning to

THE DIRECTORY, Brookline 2930

Massachusetts General Hospital

Pay Consultation Clinic

To aid in diagnosis in cases requiring the advice of several specialists, members of the staff of the Massachusetts General Hospital will hold clinics at the hospital Tuesday and Friday afternoons at 1.30 P.M.

Physicians desiring to make use of the clinic should refer their cases by letter addressed to the Consultation Clinic, giving a brief history. The object being to establish a diagnosis, no treatment will be given, nor will patients be admitted to the hospital except to complete an examination which cannot be completed in the limited time of the clinic.

Patients are referred back to the doctor who sends them to us. Several visits may be necessary to establish a diagnosis, and when ordered by the clinic staff, no additional charge will be made for such visits. Upon completion of the examination a report will be sent to the doctor who refers the case.

No appointment is necessary.

No treatment given.

Hours: Tuesdays and Fridays, 1.30 P.M. to 2 P.M

A letter from a doctor is required in every case.

Consultation	**$10.00**
X-Ray	**3.00 to 10.00**
Laboratory examination	**2.00**
Cystoscopy	**3.00**
Electrocardiogram	**10.00**

Departments represented:

Medicine	**Surgery**
Genito-urinary	**Orthopedics**
Syphilis	**Skin Diseases**
Pediatrics	**Neurology**
Nose and Throat	**Eye and Ear**

F. A. WASHBURN, Sec'y,
General Executive Committee.

Boylston Laboratory

for physicians and surgeons

SUITE 308, 419 BOYLSTON ST., BOSTON

G. B. Whall, Manager

All forms of analytical work promptly executed
Fresh cultures of the Bacillus Bulgaricus made daily

Tel. B. B. 4200

RADIUM

STANDARD CHEMICAL CO.

RADIUM of highest purity in any quantity.

Patented glazed plaques
for superficial conditions.

Tube and Needle Applicators
for deep therapy.

Apparatus for radium emanation
installed by our Department of Physics.

All our applicators and apparatus adopted after having been proven therapeutically practicable.

U. S. Bureau of Standards Certificate.

Our Departments of Physics and Medicine give instruction in the physics and therapeutic application of Radium.

RADIUM CHEMICAL CO.
PITTSBURGH, PA.

BOSTON Little Building CHICAGO Marshall Field Annex Building SAN FRANCISCO Hearst Building
Astor Trust Bldg NEW YORK Fifth Ave. at 41st St.

For DIABETES

The best starch-free foods
are made from

LISTERS **DIABETIC** FLOUR
(PREPARED CASEIN)

Warranted strictly
starch-free and sugar-free.

Especially useful in a strictly non-carbohydrate diet.

Listers Flour is self-rising and easily made into palatable bread and pastry that satisfy diabetic hunger.
A months supply (30 boxes) $4.85

Ask us what store in your city has it – or it may be sent direct.

Made by LISTER BROS. Inc. 405 Lexington Ave. New York N.Y.

100% SHARP

Bard-Parker Knife

ASK YOUR DEALER

BARD-PARKER COMPANY, Inc. NEW YORK

Physiotherapy

The remarkable results secured in the treatment of our wounded soldiers by the various physiotherapy methods used in the U. S. Reconstruction Hospitals have attracted national attention. The value of physiotherapy has been so clearly demonstrated that the U. S. Government has equipped many of the U. S. Public Health Service Hospitals with apparatus for use in physiotherapy.

Leading physicians now realize that physiotherapy can be of great assistance to them in their general practice. It has shown its value particularly in a large number of chronic conditions, and also in the treatment of occupational injuries received by mill workers and artisans of various kinds.

The Thompson-Plaster Electrical Cabinets supply many of the modalities used in physiotherapy. Write for our booklet "Electrotherapy in the Abstract," which explains the value of these modalities, and gives the technique for their application.

* * *

CLAPP ANDERSON CO.

Specialists in high quality X-Ray and Electro-Medical Apparatus

120 BOYLSTON STREET, BOSTON, MASS.

Morse Wave Generator



The above apparatus is an instrument designed to synchronize normal muscle movements, producing definite wave muscle undulations, either for alternating or direct current effects. The former is exercise and massage and the latter to be used wherever the Galvanic current is indicated. The apparatus can be used on either the alternating or direct current without a transformer. The above features are characteristic of the apparatus.

MORSE-CHAPMAN COMPANY

462 Boylston Street, Boston, Mass.

CALCREOSE

INTESTINAL INFECTIONS

CALCREOSE is an ideal intestinal antiseptic. It is useful in cases of intestinal sepsis, either primary or secondary.

CREOSOTE is one of the few drugs which appear to have a just claim to be useful as intestinal antiseptics but it impairs the appetite and disturbs digestion, besides causing gastric distress.

CALCREOSE is free from these objections, even when taken in comparatively large doses—as high as 160 grains per day—for long periods of time.

Write for literature and samples

THE MALTBIE CHEMICAL COMPANY, Newark, N. J.

We are now manufacturing

SILVER-SALVARSAN

(The sodium salt of silver-diamino-dihydroxy-arsenobenzene)

This has been used with success in Europe for more than two years past. Silver-Salvarsan is in clinical use in the following New York hospitals and clinics:

Vanderbilt Clinic . . . (Service of Dr. Fordyce)
Skin and Cancer . . . (Service of Dr. Stetson)
Bellevue . . . . (Service of Dr. Parounragian)
Volunteer . . . . . (Service of Dr. Baketel)

HA M E T Z LAB
Trade Mark Reg. U.S. Pat. Off.

The physicians who are administering the product are well satisfied with the results obtained. Silver-Salvarsan effects a more rapid disappearance of the contagious lesions than the other forms of Salvarsan and practically no reaction follows its administration.

SILVER-SALVARSAN IS NOW READY
for general distribution to the medical profession.

H-A-METZ LABORATORIES, Inc.
One-Twenty-Two Hudson Street, New York.

HIGH TENSION — BRIDGE TO SAFETY

A well known heart specialist says: "PULVOIDS NATRIUM COMP. will quickly and safely bring about the reduction of the (high blood) pressure until the basic condition can be removed or modified by indicated treatment."


HIGH BLOOD PRESSURE
PULVOIDS NATRIUM COMPOUND
(DR M C THRUSH)
SAFE AND PROMPT RELIEF
"I have found them very useful in lowering blood pressure One patient that I had with a pressure of 300 was reduced to 205 in a week-"
Composition
Potassium nitrate, sodium nitrite, sodium bicarb, nitroglycerine and crataegus oxyacantha (tonic for heart muscle and to prevent shock) Special (green colored) sugar coating, to dissolve in intestinal tract and avoid gastric disturbance Non-toxic
DOSAGE One pulvoid 2 to 4 t.i.d increased when necessary to 12 daily, until pressure reaches normal, then reduce dose
"Can't get along without them. The worst cases of high blood pressure yield readily"

Canadian Distributor
in bottles of 100 only
R. L. GIBSON
88 Wellington St., West
Toronto

Special Cash-with-order Trial Offer to Physicians and Hospitals Only

200 for $1.00, one time only, or 1000 for $5.00 on 60 days' trial, money back if not satisfied. Trade package, 100 for 75 cts., through jobber or direct plus postage. Canada, 200 for $2.00, cash with order, duty and post paid.

Write for free 32-page brochure on High Blood Pressure by M. C. Thrush, Ph.G., Ph.M., M.D., and ask also for our price list if you dispense.

Manufactured solely by
The DRUG PRODUCTS CO., Inc.
151 Meadow St.
Long Island City, N. Y.

Only heroic measures will

Save the Pregnant Woman

who is anuric or in convulsions. Give her the undisputed benefits of alkali by starting its administration early.

Patients do not tire of drinking
KALAK WATER
as they do of other methods of taking alkali.

Each bottle carries in sparkling form several grammes of the bicarbonates of sodium, potassium, calcium and magnesium.

Kalak Water Company of N.Y.
23 City Hall Place, New York City

Doctor:-

Try our

TRADE MURDOCK'S MARK Mufood

adict of

Milk-Eggs-Malt Extract

Samples on request



Pomeroy Frame Truss *for* Hernia

Right Femoral
Leather Covered Frame Truss

Left Inguinal
Frame Truss with Oscillating Water Pad

For Large Right Inguinal Hernia. A Heavy Frame with Combination Water Pad

Right Inguinal and Left Femoral
Frame Truss with Water Pads

Our Guarantee

WITH the Frame Truss to retain securely and comfortably the Hernia of any person fitted by us. To refund the price paid if not satisfactory within sixty days' trial. To make alterations and repairs for one year without extra charge.

Right Femoral
Frame Truss with Oscillating Water Pad

POMEROY COMPANY - - - - 41 West Street, Boston

NEW YORK BROOKLYN NEWARK DETROIT CHICAGO SPRINGFIELD

PRESS OF JAMAICA PRINTING COMPANY, BOSTON, MASS.